



# JACKSON COUNTY AIRPORT- TERMINAL AREA DEVELOPMENT

JACKSON COUNTY GOVERNMENT  
500 Sky Harbor Way, Jefferson, GA 30549

CONSTRUCTION DOCUMENTS

GOODWYN MILLS CAWOOD, LLC	ARCHITECTURE, INTERIORS, CIVIL, ELECTRICAL, LANDSCAPE
PES STRUCTURAL ENGINEERS	STRUCTURAL ENGINEERING
MATHESON BALL AND ASSOCIATES	MECHANICAL & PLUMBING ENGINEERING

ALPHA SITE SET 10-29-2024

TITLE SHEET

JACKSON COUNTY AIRPORT- TERMINAL AREA DEVELOPMENT  
500 Sky Harbor Way, Jefferson, GA

ISSUE DATE  
CONSTRUCTION DOCUMENTS 12/29/24

Goodwyn Mills Cawood, LLC  
6120 Powers Ferry Road NW, Suite 200  
Atlanta, GA 30339  
T 770.952.2481  
GMCNETWORK.COM

GMC

T1

GMC # AATL230012

DRAWN BY: KP  
CHECKED BY: MN

1/30/2024 8:23:25 AM

TEMPLATE VERSION: 2021

1

2

3

4

5

6

7

8

9

10

11

12

1/29/2024 11:02:41 AM  
TEMPLATE VERSION: 2022.1

123456789101112

GENERAL NOTES

1. ALL WORK DESCRIBED, SHOWN, REFERENCED, OR OTHERWISE INDICATED IN OR ON THE DRAWINGS, PROPOSAL, ADVERTISEMENT AND SPECIFICATIONS ARE TO BE COMPLETED IN-PLACE AND SERVICEABLE ACCORDING TO THE PLANS, INSTRUCTIONS, SPECIFICATIONS, LINES AND GRADES INDICATED ON THE PLANS AND ALL APPLICABLE STATE, FEDERAL, AND MUNICIPAL CODES AND STANDARDS. INDIVIDUAL ITEMS OF WORK THAT ARE NECESSARY TO COMPLETE THE PROJECT TO THE LINES AND GRADES, WHETHER SHOWN OR DESCRIBED IN THE PLANS AND SPECIFICATIONS, ARE TO BE CONSIDERED INCIDENTAL AND ARE THE RESPONSIBILITY OF THE CONTRACTOR.

2. THE CONTRACTOR IS EXPECTED TO CAREFULLY EXAMINE THE PLANS, PROJECT MANUAL AND SITE OF THE WORK. THEREFORE, IT WILL BE ASSUMED THAT THE BIDDER HAS SATISFIED HIMSELF AS TO THE CONDITIONS TO BE ENCOUNTERED IN REGARDS TO THE CHARACTER, QUALITY, AND QUANTITIES OF WORK TO BE PERFORMED AND MATERIALS TO BE FURNISHED, AND AS TO THE REQUIREMENTS OF THE PLANS, SPECIFICATIONS AND CONTRACT. THE SUBMISSION OF A PROPOSAL BY A BIDDER WILL BE CONSIDERED PRIMA FACIE EVIDENCE THAT THE BIDDER HAS MADE SUCH AN EXAMINATION.

3. THE WORK ON THIS PROJECT SHALL ADHERE TO THE FOLLOWING SPECIFICATIONS, STANDARDS AND/OR REGULATIONS:

-ENVIRONMENTAL PROTECTION DIVISION, GEORGIA (EPD) AND THE UNITED STATES ENVIRONMENTAL PROTECTION AGENCY (EPA) -- "BEST MANAGEMENT PRACTICES MANUAL" AND THE REQUIREMENTS OF THE SITE SPECIFIC NPDES DISCHARGE PERMIT ISSUED FOR THIS PROJECT.  
-GEORGIA DEPARTMENT OF TRANSPORTATION STANDARD SPECIFICATIONS FOR HIGHWAY CONSTRUCTION (LATEST EDITION) .  
-JACKSON COUNTY STANDARDS AND SPECIFICATIONS.  
-CITY OF JEFFERSON STANDARDS AND SPECIFICATIONS.  
-THE DRAWINGS AND SPECIFICATIONS.  
-APPLICABLE FAA STANDARDS AND SPECIFICATIONS/ADVISORY CIRCULARS INCLUDING, BUT MAY NOT BE LIMITED TO:  
-150/5210-5, 150/5340-18, 150/5340-1, 150/5370-2G, 150/5220-23, AND FEDERAL SPECIFICATIONS KKK-A-1822.  
  
\*IF CONFLICTS ARISE BETWEEN THESE REQUIREMENTS, THE MORE STRINGENT SHALL APPLY.

4. THE CONTRACTOR IS RESPONSIBLE FOR HAVING ALL EXISTING UTILITIES LOCATED PRIOR TO CONSTRUCTION, INCLUDING STUBOUTS. EXISTING UTILITIES SHOWN HAVE BEEN DRAWN USING THE BEST AVAILABLE INFORMATION AND HAVE NOT BEEN FIELD VERIFIED. ALL EXISTING UTILITIES TO BE UNCOVERED AND VERIFIED AS TO SIZE, LOCATION, ELEVATION AND CONDITION PRIOR TO COMMENCEMENT OF CONSTRUCTION.

5. THE CONTRACTOR SHALL COORDINATE WITH THE UTILITY COMPANIES CONCERNING CONFLICTS, RELOCATION, REMOVAL, AND INTERRUPTIONS OF SERVICE.

6. THE CONTRACTOR IS RESPONSIBLE FOR ALL COST ASSOCIATED WITH REMOVING AND/OR RELOCATING EXISTING UTILITIES AND STRUCTURES TO CONSTRUCT THE IMPROVEMENTS SHOWN IN THESE PLANS. THE CONTRACTOR SHALL NOT RECEIVE ADDITIONAL COMPENSATION FOR REMOVING AND/OR RELOCATING ANY EXISTING ITEMS, WITHIN THE LIMITS OF WORK.

7. THE CONTRACTOR IS RESPONSIBLE FOR ALL COSTS ASSOCIATED WITH ALL PERMITS FOR THIS PROJECT. THE CONTRACTOR SHALL BE IN POSSESSION OF ALL REQUIRED PERMITS PRIOR TO ANY CONSTRUCTION EFFORTS.

8. ANY CHANGES OR REVISIONS MADE TO THE SITE PLANS SHALL BE SUBMITTED FOR APPROVAL TO THE CITY OF JEFFERSON AND ALL OTHER PERTINENT AGENCIES.

9. THE CONTRACTOR SHALL BE RESPONSIBLE FOR VERIFYING THE EXTENT, LOCATION AND ELEVATION OF THE EXISTING IMPROVEMENTS. IF ANY SIGNIFICANT DIFFERENCE IN SITE CONDITION OR ELEVATION IS FOUND, THE CONTRACTOR SHALL NOTIFY THE PROJECT ENGINEER IMMEDIATELY.

10. SEE THE REPORT OF GEOTECHNICAL INVESTIGATION PERFORMED BY GOODWYN MILLS CAWOOD, LLC., DATE AUGUST 25, 2022 FOR GENERAL EARTHWORK AND PAVEMENT EVALUATIONS AND RECOMMENDATIONS. SPECIFIC CONSTRUCTION CONCERNS AND ACTUAL CONSTRUCTION MEANS AND METHODS ARE THE RESPONSIBILITY OF THE CONTRACTOR. THE CONTRACTOR SHALL BE RESPONSIBLE FOR OBTAINING AND FAMILIARIZING HIMSELF WITH THE INVESTIGATION AND THE EVALUATIONS AND RECOMMENDATIONS CONTAINED THEREIN.

11. ALL DIMENSIONS SHOWN ARE TO FACE OF CURB, CENTER OF STRIPE, FACE OF BUILDING OR AS SPECIFIED IN THE PLANS.

12. THE CONTRACTOR SHALL COORDINATE THE ELECTRICAL CONNECTION POINT, SERVICE, SIZE, POLE LOCATIONS, AND TRANSFORMER LOCATIONS WITH THE SERVICE PROVIDER PRIOR TO CONSTRUCTION ACTIVITIES.

13. THE CONTRACTOR SHALL PAY ALL CONNECTION COSTS AND FEES, INCLUDING BUT NOT LIMITED TO TAPPING FEES, METER COSTS, SETTING CHARGES, AND CONNECTION CHARGES.

14. IF BLASTING IS REQUIRED, THE CONTRACTOR WILL NEED PRIOR BE RESPONSIBLE FOR ALL PRE-BLAST SURVEYS AND ANY INCIDENTS ASSOCIATED WITH THE BLASTING.

15. ALL EXISTING AND NEW STORM DRAINAGE INLETS, STRUCTURES, AND PIPES SHALL BE CLEANED OF TRASH AND SEDIMENTS ON A REGULAR BASIS, WEEKLY AT A MINIMUM, SO AS NOT TO ALLOW DOWNSTREAM POLLUTION OF RECEIVING WATERS OR THE ESCAPING OF SEDIMENTS OFF SITE.

16. THE CONTRACTOR WILL BE RESPONSIBLE FOR TEMPORARY DIVERSION BERMS AND/OR DITCHES AND SHALL BE PROVIDED AS REQUIRED DURING CONSTRUCTION TO PROTECT WORK AREAS FROM UPSLOPE RUNOFF AND/OR TO DIVERT SEDIMENT-LADEN WATER TO APPROPRIATE TRAPS OR STABLE OUTLETS. THIS TEMPORARY DRAINAGE OF RUNOFF IS CONSIDERED INCIDENTAL TO THE BID.

17. THE CONTRACTOR SHALL BE RESPONSIBLE FOR KEEPING DUST TO A MINIMUM THROUGH THE USE OF WATER TRUCKS OR OTHER DUST CONTROLLING METHODS THROUGHOUT THE CONSTRUCTION PERIOD.

18. THE CONTRACTOR SHALL BE RESPONSIBLE FOR KEEPING EROSION AND SILTATION OFF OF ADJACENT AND DOWNSTREAM PROPERTIES AND/OR ADJOINING SITES, AT HIS EXPENSE. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE REMOVAL OF SEDIMENTS AND DEBRIS ESCAPING THIS PROJECT SITE, THE REMEDIATION AND/OR REPAIR OF ANY DAMAGE THAT MAY OCCUR AS A RESULT TO ADJOINING AND/OR DOWNSTREAM AFFECTED PROPERTIES OR OFFSITE STRUCTURES, AND ANY FINES OR PENALTIES LEVIED AGAINST THE PROJECT BY REGULATORY AGENCIES DUE TO DEFICIENCIES OF CONTROL MEASURES.

19. ALL DISTURBED AND REGRADED AREAS NOT TO BE PAVED SHALL RECEIVE TOPSOIL AND BE SEEDED AND MULCHED ACCORDING TO GDOT. PERMANENT SEEDING SCHEDULES COVERED WITH SOLID SOD, OR AS SHOWN ON THE LANDSCAPE PLAN (IF ANY), LOCALIZED EROSION AND RILLS SHALL BE REPAIRED AS NECESSARY AT THE CONTRACTORS EXPENSE. AREAS TO BE SEEDED SHALL RECEIVE 4" OF TOPSOIL AND AREAS TO BE SODDED SHALL RECEIVE 2" (MIN.) OF TOPSOIL. ACCOUNT FOR THICKNESS OF TOPSOIL WITH RESPECT TO FINISHED GRADES.

20. THE CONTRACTOR MUST ADJUST ALL VALVE BOXES, COVERS, METERS, MANHOLE RIMS, AND OTHER WATER, STORM, POWER, TELECOMMUNICATIONS AND SANITARY SEWER SERVICE APPURTENANCES TO FINAL GRADE. THE COST OF THESE ADJUSTMENTS SHALL BE INCLUDED IN THE BID.

21. THESE PLANS HAVE NOT BEEN APPROVED BY ALL OF THE REGULATORY AGENCIES AT THIS TIME. THE CONTRACTOR SHALL ANTICIPATE REVISIONS AND/OR DELAYS ASSOCIATED WITH OBTAINING PLAN APPROVAL. THE CONTRACTOR SHALL NOT RECEIVE ADDITIONAL COMPENSATION FOR SAID DELAYS.

22. ALL UTILITY BORES SHALL BE A MINIMUM OF 4 FT DEEP. ANY DAMAGE TO EXISTING STREETS OR DRIVES RESULTING FROM A UTILITY BORE SHALL BE REPAIRED BY THE CONTRACTOR AT NO ADDITIONAL COST TO THE OWNER.

23. THE CONTRACTOR WILL BE RESPONSIBLE FOR REPAIR TO PUBLIC AND PRIVATE ROADS CAUSED BY HIS ACTIVITIES. IT IS THE CONTRACTOR'S RESPONSIBILITY TO MEET WITH PRIVATE ENTITIES, STATE, CITY AND COUNTY OFFICIALS TO AGREE UPON AND RECORD THE CONDITIONS OF THE ROADS BEFORE CONSTRUCTION COMMENCES.

24. ALL PAVING WORK SHALL BE DONE IN ACCORDANCE WITH THE LATEST EDITION OF GDOT'S STANDARDS AND SPECIFICATIONS. ALL STRIPING AND SIGNAGE SHALL BE IN ACCORDANCE WITH THE LATEST EDITION OF THE MUTCD.

25. IT IS THE CONTRACTOR'S RESPONSIBILITY TO COORDINATE THE CONSTRUCTION SEQUENCE OF ALL UNDERGROUND UTILITIES WITH THE BUILDING FOOTINGS/FOUNDATIONS, RETAINING WALLS, COLUMNS, STEPS, LIGHT POLES, INLETS, MANHOLES AND ALL OTHER ABOVE OR BELOW GRADE IMPROVEMENTS.

26. THE CONTRACTOR SHALL INCLUDE IN HIS BID ALL COSTS ASSOCIATED WITH SHORING/STABILIZING EXISTING UTILITIES DURING CONSTRUCTION OF THE PROPOSED IMPROVEMENTS.

27. THE CONTRACTOR IS RESPONSIBLE FOR THE COST OF ANY AND ALL WATER AND SANITARY SEWER FEES, TAPPING FEES, CONNECTION FEES, ETC.

28. THE CONTRACTOR SHALL PROVIDE THE OWNER AND ENGINEER WITH AN AS-BUILT SURVEY OF THE SANITARY SEWER LINE, STORM SEWER SYSTEM AND POND. THE SURVEY SHALL INCLUDE ALL PIPES, MANHOLES, STORM SEWER STRUCTURES, POND OUTLET STRUCTURE, SPILLWAYS AND THE POND. THE SURVEY SHALL BE PERFORMED ON THE SAME DATUM AND COORDINATE SYSTEM OF THESE PLANS. THE SURVEY SHALL BE PREPARED IN ACCORDANCE WITH THE STANDARDS OF PRACTICE AND STAMPED BY A SURVEYOR LICENSED IN THE STATE OF GEORGIA.

29. THE CONTRACTOR SHALL PLACE SANITARY SEWER CLEANOUTS A MAXIMUM OF 75 FEET ON CENTER ALONG THE SANITARY SEWER LATERALS.

30. ALL PIPES SHALL BE INSTALLED PER THE PLANS, SPECIFICATIONS, GEOTECHNICAL REPORT AND MANUFACTURERS SPECIFICATIONS, IF CONFLICTS ARISE THE MORE STRINGENT SHALL APPLY.

31. THE CONTRACTOR SHALL BE RESPONSIBLE FOR ASSURING ALL TRENCH EXCAVATIONS FOR THIS PROJECT ARE IN ACCORDANCE WITH OSHA REGULATIONS.

32. IT IS THE CONTRACTOR'S RESPONSIBILITY TO VERIFY ALL INVERT ELEVATIONS, PERCENT OF GRADE, PIPE SIZES, ETC. AS THE IMPROVEMENTS ARE INSTALLED. THE CONTRACTOR IS RESPONSIBLE FOR VERIFYING SANITARY SEWER GRADES FOR COMPLIANCE WITH THE MINIMUM REQUIREMENTS PRIOR TO FINAL GRADING AND PAVING OPERATIONS.

33. IT IS THE CONTRACTOR'S RESPONSIBILITY TO SATISFY HIMSELF OF THE ACCURACY OF THE SURVEY INFORMATION PRIOR TO COMMENCING CONSTRUCTION.

GRADING AND DRAINAGE NOTES:

1. UNSTABLE AND PUMPING SUB GRADE CONDITIONS MAY OCCUR DURING SITE PREPARATION AND UNDERCUTTING OPERATIONS. PROPER PROTECTION OF SUB GRADE, DRAINAGE AND DEWATERING WILL BE CRITICAL TO SITE CONSTRUCTION EFFORTS. IT SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR TO MINIMIZE EQUIPMENT TRAFFIC ACROSS THE SITE. EVERY EFFORT SHALL BE MADE TO LOCALIZE EQUIPMENT STAGING AND TRAFFIC TO SPECIFIC AREAS AND LIMIT THE AMOUNT OF UNDERCUTTING AND SOIL STABILIZATION THAT MAY BE NEEDED. THE CONTRACTOR SHALL REFER TO THE GEOTECHNICAL REPORT FOR FURTHER RECOMMENDATIONS.

2. ALL DRAINAGE STRUCTURES, INLETS BOXES, MANHOLES, ETC. SHALL BE POURED IN PLACE OR PRE CAST CONCRETE AS REQUIRED.

3. BRICK WILL ONLY BE ALLOWED TO ADJUST GRADE ON STORM MANHOLES. THE MAXIMUM ALLOWABLE HEIGHT OF BRICK SHALL BE 11 INCHES.

4. ALL DRAINAGE STRUCTURES, INLET BOXES, AND CATCH BASINS SHALL HAVE 2" WEEP HOLES FORMED, OR DRILLED, ON ALL SIDES WHERE DRAINAGE PIPES DO NOT INTERFERE WITH THEM. ALL WEEP HOLES SHALL HAVE GRAVEL WRAPPED WITH FILTER FABRIC AT THEIR INTERFACE WITH BACK FILL TO AID GROUNDWATER FLOW TO THE WEEP HOLE.

5. ALL GRADING OPERATIONS SHALL BE MONITORED BY A QUALIFIED GEOTECHNICAL CONSULTANT AS CHOSEN AND PAID FOR BY THE OWNER. THE CONTRACTOR SHALL BE RESPONSIBLE FOR NOTIFYING SAID CONSULTANT IN ADVANCE OF ALL REQUIRED TESTING AND SECURING COPIES OF RESULTING REPORTS.

6. ALL EXCESS EXCAVATION CREATED BY GRADING OPERATIONS SHALL BE REMOVED AND LEGALLY DISPOSED OF OFF SITE.

7. ALL SPOT ELEVATIONS SHOWN REFLECT ELEVATIONS AT GUTTER LINE, ASPHALT, OR FINISHED GROUND ELEVATION, UNLESS OTHERWISE NOTED. TOP AND BOTTOM ELEVATIONS FOR RETAINING WALLS (IF ANY) REPRESENT THE FINISHED GROUND ELEVATION AT THE WALL, NOT FOOTINGS, RAILINGS ETC.

8. ALL STORM DRAINAGE PIPE LABELED "RCP" SHALL BE CLASS 3 MINIMUM REINFORCED CONCRETE PIPE WITH TYPE 1, 2 OR 3 BEDDING UNLESS SPECIFICALLY SHOWN OTHERWISE IN THE PLANS. IF ANOTHER TYPE OF PIPE IS SPECIFIED, BEDDING AND BACKFILL SHALL BE AS PER LATEST GDOT STANDARDS AND SPECS.

9. ALL REINFORCED CONCRETE STORM SEWER PIPE JOINTS SHALL BE WRAPPED WITH FILTER CLOTH. THE PIPE DOWNSTREAM OF THE POND OUTLET SHALL HAVE WATER TIGHT JOINTS.

10. ALL EXISTING AND NEW STORM DRAINAGE INLETS, STRUCTURES, AND PIPES SHALL BE CLEANED OF TRASH AND SEDIMENTS ON A REGULAR BASIS, WEEKLY AT A MINIMUM, SO AS NOT TO ALLOW DOWNSTREAM POLLUTION OF RECEIVING WATERS OR THE ESCAPING OF SEDIMENTS OFF SITE.

ITEM No.	SPEC NO.	DESCRIPTION	ESTIMATED QUANTITY	UNIT OF MEASURE
1.	151-1000	MOBILIZATION	1	LS
2.	202-1000	CLEARING AND GRUBBING	6.0	AC
3.	P-152-401-01	UNCLASSIFIED EXCAVATION	3,432.0	CY
4.	P-152-405-01	BORROW EXCAVATION	2,252	CY
Paving				
5.	310-5080	GR AGGR BASE CRS, 8 INCH, INCL MATL	6,352	SY
6.	402-3190	RECYCLED ASPH CONC 19 MM SUPERPAVE, GP 1 OR 2, INCL POLYMER MODIFIED BITUM MATL & H LIME ( 2 IN LIFT)	610	TN
7.	402-3103	RECYCLED ASPH CONC 9.5 MM SUPERPAVE, TYPE II, GP 2 ONLY, INCL BITUM MATL & H LIME (2 INCH LIFT)	610	TN
8.	412-1000	BITUMINOUS PRIME	1,053.0	GL
9.	413-0750	TACK COAT	278	GL
10.	441-0104	CONC SIDEWALK, 4 IN	284	SY
11.	441-5002	CONCRETE HEADER CURB, 6 IN, TP 2	806	LF
12.	652-0095	PAVEMENT MARKING, HANDICAP SYMBOL	2	EA
13.	652-5451	SOLID TRAFFIC STRIPE, 5 IN, WHITE	718	LF
14.	652-5452	SOLID TRAFFIC STRIPE, 5 IN, YELLOW	230	LF
Drainage				
15.	500-3800	CLASS A CONCRETE, INCL REINF STEEL (HEADWALL, 18 IN)	2	CY
16.	550-1180	STORM DRAIN PIPE, 18 IN, H 1-10	319	LF
17.	550-1360	STORM DRAIN PIPE, 36 IN, H 1-10	439	LF
18.	550-4118	FLARED END SECTION 18 IN, SIDE DRAIN	1	EA
19.	D-44	POND OUTLET STRUCTURE	1	EA
20.	610-5715	REM CATCH BASIN, DROP INLET, OR JCT BOX	1	EA
21.	668-2100	DROP INLET, GP 1 (PEDESTAL TOP)	3	EA
Erosion Control				
22.	163-0232	TEMPORARY GRASSING	3	AC
23.	163-0240	MULCH	430	TN
24.	163-0301	CONSTRUCT AND REMOVE CONSTRUCTION EXITS	1	EA
25.	163-0529	CONSTRUCT AND REMOVE TEMPORARY STONE CHECK DAMS	48	LF
26.	163-0001	STORM DRAIN OUTLET PROTECTION	25	SY
27.	163-0550	CONSTRUCT AND REMOVE INLET SEDIMENT TRAP	6	EA
28.	165-0030	MAINTENANCE OF TEMPORARY SILT FENCE, TP C	1,656	LF
29.	163-0542	FILTER RING	1	EA
30.	D-22B	FLOATING SURFACE SKIMMER	1	EA
31.	165-0105	MAINTENANCE OF INLET SEDIMENT TRAP	6	EA
32.	700-6910	PERMANENT GRASSING	3	AC
33.	708-1000	PLANT TOPSOIL	492	CY
Utility				
34.	610-0215	REM CHAIN LINK FENCE, 6 FT W/BARBED WIRE & EXT ARMS & GATES	827	LF
35.	660-1905	GATE VALVE, 2 IN	1	EA
36.	660-2042	SEWER LATERAL (CLEANOUTS INCLUDED)	100	LF
37.	670-3010	TAPPING VALVE	1	EA

NOTE: ALL WORK SHALL BE DONE IN ACCORDANCE WITH THE GEORGIA DEPARTMENT OF TRANSPORTATION STANDARD SPECIFICATIONS CONSTRUCTION OF TRANSPORTATION SYSTEMS, 2021 EDITION, OR AS MODIFIED BY THE CONTRACT DOCUMENTS. THE CONTRACTOR SHALL BE REQUIRED TO HAVE A COPY OF THE GEORGIA DEPARTMENT OF TRANSPORTATION'S STANDARD SPECIFICATIONS AND CONSTRUCTION STANDARD DETAILS ON THE PROJECT SITE AT ALL TIMES DURING CONDRUCTION.

123456789101112

GENERAL NOTES

1/29/2024 11:02:41 AM

1/29/2024

CONSTRUCTION DEVELOPMENT

GRADING AND DRAINAGE NOTES:

1. UNSTABLE AND PUMPING SUB GRADE CONDITIONS MAY OCCUR DURING SITE PREPARATION AND UNDERCUTTING OPERATIONS. PROPER PROTECTION OF SUB GRADE, DRAINAGE AND DEWATERING WILL BE CRITICAL TO SITE CONSTRUCTION EFFORTS. IT SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR TO MINIMIZE EQUIPMENT TRAFFIC ACROSS THE SITE. EVERY EFFORT SHALL BE MADE TO LOCALIZE EQUIPMENT STAGING AND TRAFFIC TO SPECIFIC AREAS AND LIMIT THE AMOUNT OF UNDERCUTTING AND SOIL STABILIZATION THAT MAY BE NEEDED. THE CONTRACTOR SHALL REFER TO THE GEOTECHNICAL REPORT FOR FURTHER RECOMMENDATIONS.
2. ALL DRAINAGE STRUCTURES, INLETS BOXES, MANHOLES, ETC. SHALL BE POURED IN PLACE OR PRE CAST CONCRETE AS REQUIRED.
3. BRICK WILL ONLY BE ALLOWED TO ADJUST GRADE ON STORM MANHOLES. THE MAXIMUM ALLOWABLE HEIGHT OF BRICK SHALL BE 11 INCHES.
4. ALL DRAINAGE STRUCTURES, INLET BOXES, AND CATCH BASINS SHALL HAVE 2" WEEP HOLES FORMED, OR DRILLED, ON ALL SIDES WHERE DRAINAGE PIPES DO NOT INTERFERE WITH THEM. ALL WEEP HOLES SHALL HAVE GRAVEL WRAPPED WITH FILTER FABRIC AT THEIR INTERFACE WITH BACK FILL TO AID GROUNDWATER FLOW TO THE WEEP HOLE.
5. ALL GRADING OPERATIONS SHALL BE MONITORED BY A QUALIFIED GEOTECHNICAL CONSULTANT AS CHOSEN AND PAID FOR BY THE OWNER. THE CONTRACTOR SHALL BE RESPONSIBLE FOR NOTIFYING SAID CONSULTANT IN ADVANCE OF ALL REQUIRED TESTING AND SECURING COPIES OF RESULTING REPORTS.
6. ALL EXCESS EXCAVATION CREATED BY GRADING OPERATIONS SHALL BE REMOVED AND LEGALLY DISPOSED OF OFF SITE.
7. ALL SPOT ELEVATIONS SHOWN REFLECT ELEVATIONS AT GUTTER LINE, ASPHALT, OR FINISHED GROUND ELEVATION, UNLESS OTHERWISE NOTED. TOP AND BOTTOM ELEVATIONS FOR RETAINING WALLS (IF ANY) REPRESENT THE FINISHED GROUND ELEVATION AT THE WALL, NOT FOOTINGS, RAILINGS ETC.
8. ALL STORM DRAINAGE PIPE LABELED "RCP" SHALL BE CLASS 3 MINIMUM REINFORCED CONCRETE PIPE WITH TYPE 1, 2 OR 3 BEDDING UNLESS SPECIFICALLY SHOWN OTHERWISE IN THE PLANS. IF ANOTHER TYPE OF PIPE IS SPECIFIED, BEDDING AND BACKFILL SHALL BE AS PER LATEST GDOT STANDARDS AND SPECS.
9. ALL REINFORCED CONCRETE STORM SEWER PIPE JOINTS SHALL BE WRAPPED WITH FILTER CLOTH. THE PIPE DOWNSTREAM OF THE POND OUTLET SHALL HAVE WATER TIGHT JOINTS.
10. ALL EXISTING AND NEW STORM DRAINAGE INLETS, STRUCTURES, AND PIPES SHALL BE CLEANED OF TRASH AND SEDIMENTS ON A REGULAR BASIS, WEEKLY AT A MINIMUM, SO AS NOT TO ALLOW DOWNSTREAM POLLUTION OF RECEIVING WATERS OR THE ESCAPING OF SEDIMENTS OFF SITE.

ITEM No.	SPEC NO.	DESCRIPTION	ESTIMATED QUANTITY	UNIT OF MEASURE
1.	151-1000	MOBILIZATION	1	LS
2.	202-1000	CLEARING AND GRUBBING	6.0	AC
3.	P-152-401-01	UNCLASSIFIED EXCAVATION	3,432.0	CY
4.	P-152-405-01	BORROW EXCAVATION	2,252	CY
Paving				
5.	310-5080	GR AGGR BASE CRS, 8 INCH, INCL MATL	6,352	SY
6.	402-3190	RECYCLED ASPH CONC 19 MM SUPERPAVE, GP 1 OR 2, INCL POLYMER MODIFIED BITUM MATL & H LIME (2 IN LIFT)	610	TN
7.	402-3103	RECYCLED ASPH CONC 9.5 MM SUPERPAVE, TYPE II, GP 2 ONLY, INCL BITUM MATL & H LIME (2 INCH LIFT)	610	TN
8.	412-1000	BITUMINOUS PRIME	1,053.0	GL
9.	413-0750	TACK COAT	278	GL
10.	441-0104	CONC SIDEWALK, 4 IN	284	SY
11.	441-5002	CONCRETE HEADER CURB, 6 IN, TP 2	806	LF
12.	652-0095	PAVEMENT MARKING, HANDICAP SYMBOL	2	EA
13.	652-5451	SOLID TRAFFIC STRIPE, 5 IN, WHITE	718	LF
14.	652-5452	SOLID TRAFFIC STRIPE, 5 IN, YELLOW	230	LF
Drainage				
15.	500-3800	CLASS A CONCRETE, INCL REINF STEEL (HEADWALL, 18 IN)	2	CY
16.	550-1180	STORM DRAIN PIPE, 18 IN, H 1-10	319	LF
17.	550-1360	STORM DRAIN PIPE, 36 IN, H 1-10	439	LF
18.	550-4118	FLARED END SECTION 18 IN, SIDE DRAIN	1	EA
19.	D-44	POND OUTLET STRUCTURE	1	EA
20.	610-5715	REM CATCH BASIN, DROP INLET, OR JCT BOX	1	EA
21.	668-2100	DROP INLET, GP 1 (PEDESTAL TOP)	3	EA
Erosion Control				
22.	163-0232	TEMPORARY GRASSING	3	AC
23.	163-0240	MULCH	430	TN
24.	163-0301	CONSTRUCT AND REMOVE CONSTRUCTION EXITS	1	EA
25.	163-0529	CONSTRUCT AND REMOVE TEMPORARY STONE CHECK DAMS	48	LF
26.	163-0001	STORM DRAIN OUTLET PROTECTION	25	SY
27.	163-0550	CONSTRUCT AND REMOVE INLET SEDIMENT TRAP	6	EA
28.	165-0030	MAINTENANCE OF TEMPORARY SILT FENCE, TP C	1,656	LF
29.	163-0542	FILTER RING	1	EA
30.	D-22B	FLOATING SURFACE SKIMMER	1	EA
31.	165-0105	MAINTENANCE OF INLET SEDIMENT TRAP	6	EA
32.	700-6910	PERMANENT GRASSING	3	AC
33.	708-1000	PLANT TOPSOIL	492	CY
Utility				
34.	610-0215	REM CHAIN LINK FENCE, 6 FT W/BARBED WIRE & EXT ARMS & GATES	827	LF
35.	660-1905	GATE VALVE, 2 IN	1	EA
36.	660-2042	SEWER LATERAL (CLEANOUTS INCLUDED)	100	LF
37.	670-3010	TAPPING VALVE	1	EA

NOTE: ALL WORK SHALL BE DONE IN ACCORDANCE WITH THE GEORGIA DEPARTMENT OF TRANSPORTATION STANDARD SPECIFICATIONS CONSTRUCTION OF TRANSPORTATION SYSTEMS, 2021 EDITION, OR AS MODIFIED BY THE CONTRACT DOCUMENTS. THE CONTRACTOR SHALL BE REQUIRED TO HAVE A COPY OF THE GEORGIA DEPARTMENT OF TRANSPORTATION'S STANDARD SPECIFICATIONS AND CONSTRUCTION STANDARD DETAILS ON THE PROJECT SITE AT ALL TIMES DURING CONDRUCTION.

GENERAL NOTES

JACKSON COUNTY AIRPORT  
NEW TERMINAL  
JACKSON COUNTY, GEORGIA

ISSUE DATE

1/29/2024

CONSTRUCTION DEVELOPMENT

Goodwyn Mills Cawood, LLC

6120 Powers Ferry Road NW, Suite 200

Atlanta, GA 30339

T 770.952.2481

GMCNETWORK.COM

NOT FOR CONSTRUCTION

C-001  
Sheet X of X


GMC # TAT1230006


DRAWN BY:

Autor

CHECKED BY:


Checker





## GENERAL NOTES


3. THE PROJECT IS SUBJECT TO ALL INSPECTIONS PROVIDED IN THE CONTRACT DOCUMENTS AND TO INSPECTIONS BY REPRESENTATIVES OF THE AIRPORT, THE CITY OF JEFFERSON, THE FEDERAL AVIATION ADMINISTRATION (FAA), THE GEORGIA ENVIRONMENTAL PROTECTION DIVISION (EPD), THE GEORGIA DEPARTMENT OF TRANSPORTATION (GDOT) AND JACKSON COUNTY.
2. THE CONTRACTOR SHALL COORDINATE ALL CONSTRUCTION ACTIVITIES WITH THE ENGINEER.
3. THE CONSTRUCTION EQUIPMENT STORAGE/STAGING AREA IS AS SHOWN. ANY DAMAGES CAUSED BY THE CONTRACTOR'S USE OF THESE AREAS MUST BE REPAIRED TO THE SATISFACTION OF THE OWNER.
4. SUFFICIENT VACUUM TYPE SWEEPERS AND CLEANING EQUIPMENT SHALL BE PROVIDED IN ORDER THAT ALL WASTE, LOOSE MATERIAL, AND DEBRIS CAN BE REMOVED FROM ALL AIRPORT OPERATIONS AREAS. ALL LOOSE MATERIAL SHALL BE COMPLETELY REMOVED FROM PAVED AND TURFED AREAS WITHIN SAFETY AREAS. PAVEMENT CLEANING EQUIPMENT SHALL BE MAINTAINED ON SITE AT ALL TIMES IN SUFFICIENT QUANTITY AND CAPACITY TO CLEAN ALL PAVEMENTS.
5. THE CONTRACTOR MUST VERIFY THE EXACT LOCATION OF EXISTING UNDERGROUND ELECTRICAL CABLES. IN THE EVENT THAT THE CONTRACTOR DAMAGES A CABLE, THE ENGINEER AND THE AIRPORT MUST BE NOTIFIED IMMEDIATELY. THE REPAIR MUST BE STARTED IMMEDIATELY AND CONTINUE UNTIL COMPLETED. ALL SUCH REPAIRS SHALL BE AT THE CONTRACTOR'S EXPENSE AND SHALL BE INSPECTED AND APPROVED BY THE OWNER PRIOR TO BACKFILLING BY THE CONTRACTOR. IF REQUIRED BY THE ENGINEER, THE CONTRACTOR SHALL SUPPLY AND INSTALL A CONCRETE SPLICE MARKER AT ALL APPLICABLE LOCATIONS.
6. THE LOCATION OF ACCESS ROUTES ON THE AIRPORT SITE ARE AS SHOWN AND ARE SUBJECT TO CHANGE. IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO COORDINATE OFF-SITE ACCESS ROUTES (STATE HIGHWAYS, LOCAL ROADS, OR CITY STREETS) WITH THE APPROPRIATE OWNER HAVING JURISDICTION OVER THE AFFECTED ROUTE. CONTRACTOR PERMISSION TO USE PUBLIC ROADS FOR HAULING AND ACCESS MUST BE OBTAINED FROM THE APPROPRIATE PUBLIC ENTITIES. IT IS THE SOLE RESPONSIBILITY OF THE CONTRACTOR TO OBTAIN NECESSARY PERMITS, APPROVALS, AND BONDING. THE CONTRACTOR MUST DETERMINE WHICH NON-AIRPORT ROADS MUST BE BONDED, AND MUST BOND SUCH ROADS.
7. THE BEFORE AND AFTER CONDITION OF ON-SITE ACCESS ROUTES SHALL BE JOINTLY INSPECTED AND PHOTOGRAPHED BY THE CONTRACTOR AND THE ENGINEER. ON-SITE ACCESS ROUTES SHALL BE MAINTAINED BY THE CONTRACTOR THROUGHOUT CONSTRUCTION AND RESTORED UPON COMPLETION OF CONSTRUCTION IN ACCORDANCE WITH THE CONTRACT DOCUMENTS. FENCING, DRAINAGE, GRADING, E&S CONTROLS, AND OTHER MISCELLANEOUS CONSTRUCTION REQUIRED TO CONSTRUCT ADDITIONAL HAUL ROUTES OR ACCESS POINTS ON THE AIRPORT WILL BE THE CONTRACTOR'S RESPONSIBILITY, AND SHALL BE APPROVED BY THE ENGINEER PRIOR TO THE COMMENCEMENT OF WORK. ALL ROADS TO AIRPORT FACILITIES SHALL REMAIN OPEN AND MAINTAINED AT ALL TIMES. ALL CONTRACTOR VEHICLES AND CONSTRUCTION TRAFFIC SHALL REMAIN WITHIN THE DESIGNATED CONSTRUCTION LIMITS OR HAUL ROUTES UNLESS OTHERWISE AUTHORIZED.
8. THE CONTRACTOR IS RESPONSIBLE FOR THE PROTECTION OF AIRPORT PAVEMENT AND LIGHTING DURING CONSTRUCTION. ALL DAMAGE RESULTING FROM THE CONTRACTOR'S ACTIONS SHALL BE REPAIRED IMMEDIATELY AT THE CONTRACTOR'S EXPENSE. ANY DELAYS IN REOPENING PORTIONS OF THE AIRPORT DUE TO THIS DAMAGE WILL RESULT IN THE ASSESSMENT OF LIQUIDATED DAMAGES AS SET FORTH IN THE CONTRACT DOCUMENTS.
9. THE CONTRACTOR IS RESPONSIBLE FOR ALL LIGHTING NECESSARY FOR ALL NIGHT OPERATIONS. LIGHTING WILL NEED TO BE DIRECTED OR SHADED TO PREVENT INTERFERENCE WITH AIRCRAFT, THE AIR TRAFFIC CONTROL TOWER, AND OTHER AIRPORT OPERATIONS.
10. OPEN-FLAME WELDING/TORCHES ARE PROHIBITED UNLESS ADEQUATE FIRE SAFETY PRECAUTIONS ARE PROVIDED AND THE AIRPORT OPERATOR HAS APPROVED THEIR USE.




FLASHING BEACON LIGHT DETAIL  
Not to scale

- NOTE:
1. THE YELLOW FLASHING LIGHT MUST BE MOUNTED ON THE UPPERMOST PART OF THE VEHICLE STRUCTURE.
  2. THE LIGHT MUST BE VISIBLE FROM ALL DIRECTIONS (INCLUDING THE AIR), DAY & NIGHT.
  3. HAZARD LIGHTS MUST MEET THE SPECIFICATIONS IN THE MOST CURRENT VERSION OF FEDERAL SPECIFICATIONS KKK-A-1822, AND ARFF VEHICLES MUST MEET NFPA, STATE, AND LOCAL REQUIREMENTS.
  4. LIGHTS MUST HAVE PEAK INTENSITY WITHIN THE RANGE OF 40 TO 400 CANDELAS (EFFECTIVE) FROM 0 DEGREES UP TO 10 DEGREES ABOVE THE HORIZONTAL AND FOR 360 DEGREE HORIZONTALLY. THE UPPER LIMIT OF 400 CANDELAS (EFFECTIVE) IS NECESSARY TO AVOID DAMAGE TO NIGHT VISION.
  5. FROM 10 DEGREES TO 15 DEGREES ABOVE THE HORIZONTAL PLANE, THE LIGHT OUTPUT MUST BE 1/10TH OF PEAK INTENSITY OR BETWEEN 4 AND 40 CANDELAS (EFFECTIVE).
  6. LIGHTS MUST FLASH AT 75 +/- 15 FLASHES PER MINUTE.

- STOCKPILED MATERIALS AND EQUIPMENT STORAGE ARE NOT PERMITTED WITHIN THE RSA, OFZ, RPZ, AND OFA OF AN OPERATIONAL RUNWAY. THE CONTRACTOR MUST ENSURE THAT STOCKPILED MATERIALS AND EQUIPMENT ADJACENT TO THESE AREAS ARE PROMINENTLY MARKED AND LIGHTED DURING HOURS OF RESTRICTED VISIBILITY OR DARKNESS. THIS INCLUDES DETERMINING AND VERIFYING THAT MATERIALS ARE STABILIZED AND STORED AT AN APPROVED LOCATION SO AS NOT TO BE A HAZARD TO AIRCRAFT OPERATIONS AND TO PREVENT ATTRACTION OF WILDLIFE AND FOREIGN OBJECT DAMAGE.
12. CONTRACTOR SHALL PROVIDE CONTROL FOR VEHICLE AND PEDESTRIAN ACCESS ROUTES TO PREVENT INADVERTENT OR UNAUTHORIZED ENTRY OF PERSONS, VEHICLES, OR ANIMALS ONTO THE AIRFIELD. CONTRACTOR MUST PARK AND SERVICE ALL CONSTRUCTION VEHICLES IN AN AREA DESIGNATED BY THE AIRPORT OPERATOR OUTSIDE THE OFZ AND NEVER IN THE SAFETY AREA OF AN ACTIVE RUNWAY OR TAXIWAY. PERSONAL VEHICLES NOT REQUIRED FOR CONSTRUCTION ACTIVITIES ARE NOT ALLOWED ON THE AIRFIELD.
13. CONTRACTOR SHALL CAREFULLY CONTROL AND CONTINUOUSLY REMOVE WASTE OR LOOSE MATERIALS THAT MIGHT ATTRACT WILDLIFE. CONTRACTOR PERSONNEL MUST BE AWARE OF AND AVOID CONSTRUCTION ACTIVITIES THAT CAN CREATE WILDLIFE HAZARDS ON AIRPORTS, SUCH AS TRASH AND STANDING WATER. SEEDING SHALL FOLLOW PROJECT SPECIFICATIONS TO ENSURE SEEDS DO NOT ATTRACT WILDLIFE.
14. CONTRACTOR SHALL TAKE CARE TO MAINTAIN SECURITY DURING CONSTRUCTION WHEN ACCESS POINTS ARE CREATED IN THE SECURITY FENCING TO PERMIT THE PASSAGE OF CONSTRUCTION VEHICLES OR PERSONNEL. TEMPORARY GATES IF REQUIRED SHOULD BE EQUIPPED SO THEY CAN BE SECURELY CLOSED AND LOCKED TO PREVENT ACCESS BY ANIMALS AND UNAUTHORIZED PEOPLE.
15. CONTRACTOR TO MAKE ALL REASONABLE EFFORT TO AVOID THE DISRUPTION OF WILDLIFE HABITAT.
16. CONTRACTORS OPERATING CONSTRUCTION VEHICLES AND EQUIPMENT ON THE AIRPORT MUST BE PREPARED WITH APPROPRIATE EQUIPMENT AND PROCEDURES TO EXPEDITIOUSLY CONTAIN AND CLEAN-UP SPILLS RESULTING FROM FUEL, HYDRAULIC FLUID LEAKS, OR OTHER HAZARDOUS MATERIALS. CONTRACTOR TO NOTIFY OWNER OR OWNER'S REPRESENTATIVE IMMEDIATELY IN THE EVENT OF A SPILL, LEAK, OR RELEASE OF A HAZARDOUS MATERIAL.
17. CONTRACTOR TO COORDINATE ALL ACTIVITIES ON THE AIRFIELD WITH THE OWNER WHO WILL ISSUE THE APPROPRIATE NOTICE TO AIRMEN (NOTAM).
18. IN THE EVENT OF AN EMERGENCY, THE CONTRACTOR SHALL CONTACT 911 OR THE APPROPRIATE RESPONSE AGENCY FOLLOWED IMMEDIATELY BY THE OWNER OR OWNER'S REPRESENTATIVE.
19. CONTRACTOR TO ENSURE EQUIPMENT DOES NOT PENETRATE THE IMAGINARY SURFACES DESCRIBED ON THE PART 77 DETAIL. SHOULD A CONSTRUCTION ACTIVITY REQUIRE PENETRATION OF THE SURFACES, THIS ACTIVITY MUST BE COORDINATED WELL IN ADVANCE WITH THE OWNER OR OWNER'S REPRESENTATIVE WHO WILL NOTIFY FAA.
20. SAFETY PROVISIONS DEFINED HEREIN AS WELL AS REFERENCED IN FAA AC 150/5370-2F, OPERATIONAL SAFETY ON AIRPORTS DURING CONSTRUCTION, SHALL BE FOLLOWED AT ALL TIMES. CONTRACTOR MAY BE FINED THE NON-PENAL SUM OF \$500 PER DAY FOR EACH CALENDAR DAY OF NON-COMPLIANCE AFTER BEING NOTIFIED OF NONCOMPLIANCE BY THE OWNER OR OWNER'S REPRESENTATIVE.
21. SHOULD ANY AIRCRAFT ACCIDENT OR INCIDENT OCCUR THE CONTRACTOR SHALL FIRST NOTIFY ANY FIRST RESPONDERS AND MUST IMMEDIATELY HALT WORK UNTIL DIRECTED BY THE OWNER OR OWNER'S REPRESENTATIVE TO RESUME.
22. CONTRACTOR SHALL ENSURE THAT AREAS WHERE AIRCRAFT WILL BE OPERATING ARE CLEARLY AND VISIBLY SEPARATED FROM CONSTRUCTION AREAS, INCLUDING CLOSED RUNWAYS. THROUGHOUT THE DURATION OF THE CONSTRUCTION PROJECT, CONTRACTOR SHALL VERIFY THAT THESE AREAS REMAIN CLEARLY MARKED AND VISIBLE AT ALL TIMES AND THAT MARKING, LIGHTING, SIGNS, AND VISUAL NAVIGATIONAL AIDS REMAIN IN PLACE AND OPERATIONAL.




TEMPORARY CHECKERED CONSTRUCTION  
FLAG ORANGE AND WHITE



## SECTION

PAVEMENT	SAFETY AREA WIDTH*
RUNWAY 17/35	500'

## SAFETY AREA DIMENSIONS




## PROFILE

NOTE:  
THE PART 77 SURFACE IS CENTERED ON THE RUNWAY AT THE CENTERLINE  
ELEVATION AND TO THE WIDTH INDICATED. THE PART 77 SURFACE  
IS LOCATED ON THE PROFILE OF THE EXTENDED RUNWAY CENTERLINE AT  
THE RUNWAY THRESHOLD ELEVATION TO A POINT 200' BEYOND EACH THRESHOLD.  
THE SECTION THEN RISES ALONG THE SLOPES INDICATED.

RUNWAY END	A	B	C
RUNWAY 17	250'	931.1'	34
RUNWAY 35	250'	950.5'	34

## FAR PART 77 SURFACES



- NOTES:
1. CAUTION LIGHTS TO BE RED IN COLOR AND FLASHING DURING HOURS OF DARKNESS. UNITS SHALL BE PLACED ADJACENT TO EACH OTHER. THERE WILL BE NO DIRECT PAYMENT FOR FURNISHING, INSTALLATION, OR REMOVAL OF BARRIER. UNITS MUST BE SECURED TO BARRIER.
  2. ALL BARRICADES SHALL DELINEATE THE AREA TO BE PROTECTED AND SHALL EXTEND TO 10' OFF THE EDGE OF EITHER SIDE OF ANY PAVEMENT. BARRICADES SHALL PROHIBIT AIRCRAFT AND VEHICLE ENTRY.
  3. CONTRACTOR SHALL WEIGH BARRICADES TO PREVENT DISPLACEMENT. METHOD TO BE APPROVED BY THE ENGINEER.
  4. BARRICADE TYPE AND SPACING SHALL MEET THE REQUIREMENTS OF AC 150/5370-2G.
  5. RED HAZARD LIGHTS MUST MEET THE LUMINANCE REQUIREMENTS OF THE STATE HIGHWAY DEPARTMENT.

LOW PROFILE AIRCRAFT BARRICADE  
Not to scale

Not to scale

# ALPHA SITE SET 10-29-2024

## CONSTRUCTION SAFETY AND PHASING PLAN DETAILS

**JACKSON COUNTY AIRPORT  
NEW TERMINAL  
JACKSON COUNTY, GEORGIA**

C-003

X of X sheet

CMC # TATI 330006


		DRAWN BY:	Author
		CHECKED BY:	Checker


GMCNETWORK.COM


Goodwyn Mills Cawood, LLC  
6120 Powers Ferry Road NW, Suite 200

6120 Powers Ferry Road NW, Suite 200  
Atlanta, GA 30339

T 770.952.2481










EXISTING CONDITIONS AND DEMO PLAN		JACKSON COUNTY AIRPORT NEW TERMINAL JACKSON COUNTY, GEORGIA		GMC # TATL230006	
<div>C-101</div> <div>sheet <input checked="" type="checkbox"/> of <input checked="" type="checkbox"/></div>	<div>NOT FOR CONSTRUCTION</div>	DATE		GMC	
		CONSTRUCTION		Goodwyn Mills Cavood, LLC	
		DEVELOPMENT		6120 Powers Ferry Road NW, Suite 200	
				Atlanta, GA 30339	
				T 770.952.2481	
				GMCNETWORK.COM	
		DRAWN BY: Author			
		CHECKED BY: Checker			

















<b>FENCE PHASING PLAN</b>	<b>C-104</b> <small>sheet X of X</small>		<b>JACKSON COUNTY AIRPORT NEW TERMINAL</b> JACKSON COUNTY, GEORGIA	<b>GMC</b>
			<p>Goodwyn Mills Carwood, LLC</p> <p>6120 Powers Ferry Road NW, Suite 200</p> <p>Atlanta, GA 30339</p> <p>T 770.952.2481</p> <p>GMCNETWORK.COM</p>	
JACKSON COUNTY AIRPORT NEW TERMINAL		GMC # TATL230006		
JACKSON COUNTY, GEORGIA				
DATE		ISSUE		
1/29/2024		CONSTRUCTION		
		DEVELOPMENT		
DRAWN BY:		Author		
CHECKED BY:		Checker		




SYMBOL	DESCRIPTION	SYMBOL	DESCRIPTION
①	ISLAND IDENTIFICATION NO.	FOC BOC R	FRONT OF CURB BACK OF CURB RADIUS OF CURVE










NOTE:  
1. ALL DIMENSIONS ARE TO FACE OF CURB (FOC)  
2. ALL COORDINATES AND DIMENSIONS ARE IN FEET UNLESS OTHERWISE NOTED ON PLANS




	ISSUE	DATE
	CONSTRUCTION DEVELOPMENT	1/29/2024
	DRAWN BY:	Author
	CHECKED BY:	Checker












ALPHA SITE SET 10-29-2024


INITIAL PHASE - EROSION AND SEDIMENT CONTROL PLANS	NOT FOR CONSTRUCTION	JACKSON COUNTY AIRPORT <b>NEW TERMINAL</b> JACKSON COUNTY, GEORGIA	GMC # TATL230006
C-401			
sheet X of X			

---

Goodwyn Mills Cawood, LLC  
 6120 Powers Ferry Road NW, Suite 200  
 Atlanta, GA 30339  
 T 770.952.2481  
[GMCNETWORK.COM](#)

















ISSUE	DATE
CONSTRUCTION	1/29/2024
DEVELOPMENT	
DRAWN BY:	Author
CHECKED BY:	Chester





# ALPHA SITE SET 10-29-2024

<b>JACKSON COUNTY AIRPORT NEW TERMINAL</b> JACKSON COUNTY, GEORGIA	<b>GMC</b>	Goodwyn Mills Cavood, LLC 6120 Powers Ferry Road NW, Suite 200 Atlanta, GA 30339 T 770.952.2481 <a href="http://GMCNETWORK.COM">GMCNETWORK.COM</a>
<b>FINAL PHASE - EROSION AND SEDIMENT CONTROL PLANS</b>	<b>C-403</b>	
sheet <span style="float: right;">X of X</span>		
GMC # TATL230006		
<b>ISSUE</b>	<b>DATE</b>	
CONSTRUCTION	1/29/2024	
DEVELOPMENT		
<b>DRAWN BY:</b>	<b>Author</b>	
<b>CHECKED BY:</b>	<b>Chester</b>	



SPECIES	RATE PER		PLANTING DATES		
	1,000 SQ. FT.	ACRE			
RYE	3.9 LB.	3 BU. (168 LBS.)	MOUNTAINS 7/15-12/1	PIEDMONT 8/15-1/1	COASTAL 9/1-3/1
RYEGRASS ANNUAL	0.9 LB.	40 LBS.	8/1-5/1	8/1-4/15	8/15-4/1
ANNUAL LESPEDEZA	0.9 LB.	40 LBS.	2/1-5/1	2/15-5/1	1/15-3/15
WEEDING LEVEGRASS	0.1 LB.	4 LBS.	3/15-6/15	3/15-6/15	2/15-6/15
SUDANGRASS	1.4 LB.	60 LBS.	3/1-9/1	3/1-9/1	3/1-8/15
BROWNTOP WILLET	0.9 LB.	40 LBS.	4/1-7/1	4/1-7/15	4/1-7/15
WHEAT	4.1 LB.	3 BU. (180 LBS.)	9/1-1/1	9/1-1/1	9/15-2/1

FERTILIZER REQUIREMENTS FOR TEMPORARY VEGETATION:				
Types of Species	Planting Year	Fertilizer (N-P-K)	Rate (lbs./acre)	N Top Dressing Rate (lbs./acre)
Cool season grasses	First	6-12-12	1500	50-100
	Second	6-12-12	1000	---
	Maintenance	10-10-10	400	30
Cool seaso grasses & legumes	First	6-12-12	1500	0-50
	Second	0-10-10	1000	---
	Maintenance	0-10-10	400	---
Temporary cover crops seeded alone	First	10-10-10	500	30
Warm season grasses	First	6-12-12	1500	50-100
	Second	6-12-12	800	50-100
	Maintenance	10-10-10	400	30

ANIONIC ASPHALT EMULSION	7:1	COARSE SPRAY	1,200
LATEX EMULSION	12.5:1	FINE SPRAY	235
RESIN-IN-WATER EMULSION	4:1	FINE SPRAY	300

Sod Planting Requirement		
Grass	Varieties	Growing Season
Bermudagrass	Common Tifton Tifgreen Tifdwarf	Warm Weather
Bahiagrass	Pensacola	Warm Weather
Centipede	-	Warm Weather
Zoysia	Emerald Myer	Warm Weather
Tall Fescue	Kentucky 31	Cool Weather

Fertilizer Recommendations for Sod				
Types of Plants	Planting Time	Fertilizer (N-P-K)	Rate (lb/1000 sq ft)	Nitrogen Top Dressings (lb/acre)
Cool Season Grasses	First Year	6-12-12	1500	50-100
	Second Year	10-10-10	800	50-100
Warm Season Grasses	First Year	6-12-12	400	50-100
	Second Year	10-10-10	200	50-100

Streambank Erosion Protection Measures		
Relative Costs and Complexity		
Measure	Relative Cost	Relative Complexity
Live Sod	Simple	Simple
Live Sod Planting	Simple	Simple
Live Fascine	Moderate	Moderate
Masturbation	Complex	Complex
Live cobweb Branchplanting	Complex	Complex
Conventional Vegetation	Moderate	Moderate to Simple
Conventional Bare seeding (No Sod)	Simple to Moderate	Simple to Moderate
Conventional Bare seeding (No Sod)	Moderate	Complex

Measure	Relative Cost	Relative Complexity
Live Stake Joint planting	Low	Simple
Live fascine	Low*	Simple*
Brushmats	Moderate	Moderate
Brushmats	Moderate	Moderate to Complex
Live cribwall	High	Complex
Branchpiling	High	Moderate to Complex
Conventional Vegetation	Low to Moderate	Simple to Moderate
Conventional Bank armoring (riprap)	Moderate to High	Moderate to Complex

1/29/2024 11:02:41 AM TEMPLATE VERSION: 2022.1

BEST MANAGEMENT PRACTICES NOTES:

1.

ALL BEST MANAGEMENT PRACTICES SHALL BE DEVELOPED AND MAINTAINED BY THE CONTRACTOR ACCORDING TO THE ENVIRONMENTAL PROTECTION DIVISION, GEORGIA (EPD) AND THE UNITED STATES ENVIRONMENTAL PROTECTION AGENCY (EPA) – “BEST MANAGEMENT PRACTICES MANUAL” AND THE REQUIREMENTS OF THE SITE SPECIFIC NPDES DISCHARGE PERMIT ISSUED FOR THIS PROJECT AS WELL AS THE LOCAL SOIL AND WATER CONSERVATION DISTRICT OFFICES IN EACH COUNTY.
2.

THE MAINTENANCE OF ALL BEST MANAGEMENT PRACTICES, SO AS TO BE AN EFFECTIVE BARRIER TO EROSION AND SEDIMENTATION, SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR THROUGHOUT THE DURATION OF THE CONSTRUCTION PERIOD. ALL EROSION AND SEDIMENTATION CONTROL MEASURES SHALL BE INSTALLED AND MAINTAINED IN COMPLIANCE WITH ALL ADEM AND EPA BEST MANAGEMENT PRACTICES AND THE NPDES PERMIT ASSOCIATED WITH THIS SITE. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE REPAIR, REPLACEMENT, AND/OR SUPPLEMENTATION OF ANY CONTROL MEASURES THAT ARE NOT FUNCTIONING PROPERLY. ALL EROSION AND SEDIMENTATION CONTROL MEASURES SHOWN ON THE PLANS SHALL BE CONSIDERED A MINIMUM.
3.

OTHER THAN LAND-CLEARING ACTIVITIES REQUIRED TO INSTALL THE APPROPRIATE BMP IN ACCORDANCE WITH THE BMP PLANS, ANY DOWN SLOPE EROSION AND SEDIMENT CONTROL MEASURES, ON-SITE STREAM CHANNEL PROTECTION AND UPSLOPE DIVERSION OF DRAINAGE REQUIRED BY THE BMP PLAN SHALL BE IN PLACE AND FUNCTIONAL BEFORE ANY CLEARING OR EARTH MOVING OPERATIONS BEGIN AND SHALL BE CONSTRUCTED AND MAINTAINED THROUGHOUT THE CONSTRUCTION PERIOD. TEMPORARY MEASURES MAY BE REMOVED AT THE BEGINNING OF THE WORKDAY, BUT SHALL BE REPLACED AT THE END OF THE WORKDAY.
4.

THE ANGLE FOR GRADED SLOPES AND FILLS SHALL BE NO GREATER THAN THE ANGLE WHICH CAN BE RETAINED BY VEGETATIVE COVER OR OTHER ADEQUATE EROSION CONTROL DEVICES OR STRUCTURES. ANY SLOPE OR FILL WHICH HAS BEEN GRADED SHALL WITHIN FOURTEEN (14) DAYS OF THE COMPLETION OF SUCH GRADING OR THE COMPLETION OF ANY PHASE OF GRADINGS, BE PLANTED OR OTHERWISE BE PROVIDED WITH GROUND COVER, MATERIALS, DEVICES, OR STRUCTURES SUFFICIENT TO RETAIN EROSION. THE BMPs SHALL REMAIN IN PLACE IN ACCORDANCE WITH THE BMP PLAN UNTIL THE GRADED SLOPE OR FILL IS STABILIZED.
5.

ALL HAZARDOUS SUBSTANCES USED FOR THIS PROJECT (PAINT, OIL, GREASE, AND OTHER PETROLEUM PRODUCTS) SHALL BE STORED IN ACCORDANCE WITH SPCC REGULATIONS. THESE SUBSTANCES SHALL BE STORED AWAY FROM STORM DRAINS, DITCHES, AND GUTTERS IN WATERTIGHT CONTAINERS. DISPOSAL OF THESE SUBSTANCES SHALL BE IN ACCORDANCE WITH ADEM REGULATIONS. THE CONTRACTOR SHALL PROVIDE ADEQUATE TRASH CONTAINERS ONSITE FOR THE DISPOSAL OF CONSTRUCTION MATERIALS WASTE. THE CONTRACTOR SHALL BE RESPONSIBLE FOR PREVENTING TRASH FROM ENTERING THE STORM DRAINAGE SYSTEM.
6.

ALL CONTROL MEASURES SHALL BE CHECKED, AND REPAIRED AS NECESSARY, MONTHLY IN DRY PERIODS, AND WITHIN 24 HOURS AFTER ANY RAINFALL AT THE SITE OF 0.75 INCH WITHIN A 24 HOUR PERIOD. DURING PROLONGED RAINFALLS, DAILY CHECKING AND, IF NECESSARY, REPAIRING SHALL BE DONE. THE PERMITTEE SHALL MAINTAIN WRITTEN RECORDS OF SUCH CHECKS AND REPAIRS, WHICH SHALL BE SUBJECT TO THE INSPECTION OF THE OFFICIAL AT ANY REASONABLE TIME.
7.

PROJECT AREA = 4.687 Acres. DISTURBED AREA = 4.687 +/- Acres
8.

APPROXIMATE START DATE: XX/XX/2024. APPROXIMATE END DATE: XX/XX/XXXX.
9.

EXISTING SITE CONDITIONS: CONCRETE, ASPHALT, GRASS.
10.

ALL MATERIALS SHALL BE PROPERLY STORED, NOT EXPOSED TO RAIN, AND STOCKPILED. ALL CONTAINERS SHALL BE STORED CLOSED OR IN COVER. ALL EXCESS OR WASTE MATERIAL SHALL BE DISPOSED OF PROPERLY. THE CONTRACTOR SHALL PROVIDE A CONSTRUCTION WASTE DUMPSTER OR TRAILER ON SITE FOR CONSTRUCTION WASTE. THE CONTRACTOR SHALL DISPOSE OF TRASH AND WASTE TO AN ACCEPTABLE OFFSITE FACILITY EVERY 10 DAYS MINIMUM.
11.

THERE SHALL BE NO DISTINCTLY VISIBLE FLOATING SCUM, OIL, OR OTHER MATTER CONTAINED IN THE STORM WATER DISCHARGE TO A RECEIVING WATER, MUST NOT CAUSE AN UNNATURAL COLOR (EXCEPT DYES OR OTHER SUBSTANCES DISCHARGED FOR THE PURPOSE OF ENVIRONMENTAL STUDIES AND WHICH DO NOT HAVE A HARMFUL EFFECT ON THE RECEIVING WATER), OR ODOR IN THE RECEIVING WATERS. THE STORM WATER DISCHARGE TO RECEIVING WATER MUST RESULT IN NO MATERIAL IN CONCENTRATION SUFFICIENT TO BE HAZARDOUS OR OTHERWISE DETRIMENTAL TO HUMANS, LIVESTOCK, WILDLIFE, PLANT LIFE OR FISH AND AQUATIC LIFE IN THE RECEIVING WATER.
12.

WHEN THE LAND-DISTURBING ACTIVITY IS FINISHED AND STABLE VEGETATION OR OTHER PERMANENT CONTROLS HAVE BEEN ESTABLISHED ON ALL REMAINING EXPOSED SOIL, THE OWNER OF THE LAND WHERE THE LAND-DISTURBING ACTIVITY WAS CONDUCTED, OR HIS AUTHORIZED AGENT, SHALL NOTIFY THE OFFICIAL OF THESE FACTS AND REQUEST A FINAL INSPECTION. THE OFFICIAL SHALL THEN INSPECT THE SITE WITHIN 5 WORKING DAYS AFTER RECEIPT OF NOTICE, AND MAY REQUIRE ADDITIONAL MEASURES TO STABILIZE THE SOIL AND CONTROL EROSION AND SEDIMENTATION AS REQUIRED.
13.

THE CONTRACTOR SHALL MINIMIZE THE TRACKING OF MUD AND DEBRIS ONTO PAVED ROADWAYS FROM CONSTRUCTION AREAS. THE CONTRACTOR SHALL PROVIDE A CONSTRUCTION EXIT PAD AS NOTED ON THE PLANS AND MAINTAIN IT ON A REGULAR BASIS AS AN EFFECTIVE MEASURE FOR REMOVING MUD AND DEBRIS FROM EQUIPMENT TIRES FROM BEING TRACKED FROM THE SITE ONTO ADJACENT ROADWAYS. THE CONTRACTOR SHALL BE RESPONSIBLE FOR PROVIDING A SPRAY HOSE FOR WASHING OF TIRES AND EQUIPMENT. THE PERIODIC REWORKING OF THE CONSTRUCTION EXIT PAD STONE, OR SUPPLEMENTING THE EXIT PAD WITH ADDITIONAL STONE AS REQUIRED TO ENSURE ITS CONTINUED EFFECTIVENESS THROUGHOUT THE DURATION OF THE CONSTRUCTION PERIOD. THE CONTRACTOR SHALL BE RESPONSIBLE FOR REMOVING AT HIS EXPENSE ANY MUD AND DEBRIS TRACKED OFFSITE AND ONTO ADJACENT ROADWAYS AS REQUIRED.
14.

ALL EXISTING AND NEW STORM DRAINAGE INLETS, STRUCTURES, AND PIPES SHALL BE CLEANED OF TRASH AND SEDIMENTS ON A REGULAR BASIS, WEEKLY AT A MINIMUM, SO AS NOT TO ALLOW DOWNSTREAM POLLUTION OF RECEIVING WATERS OR THE ESCAPING OF SEDIMENTS OFF SITE.
15.

TEMPORARY DIVERSION BERMS AND/OR DITCHES SHALL BE PROVIDED AS REQUIRED DURING CONSTRUCTION TO PROTECT WORK AREAS FROM UPSLOPE RUNOFF AND/OR TO DIVERT SEDIMENT-LADEN WATER TO APPROPRIATE TRAPS OR STABLE OUTLETS.
16.

THE CONTRACTOR SHALL BE RESPONSIBLE FOR KEEPING DUST TO A MINIMUM THROUGH THE USE OF WATER TRUCKS OR OTHER DUST CONTROLLING METHODS THROUGHOUT THE CONSTRUCTION PERIOD.
17.

THE CONTRACTOR SHALL BE RESPONSIBLE FOR KEEPING EROSION AND SILTATION OFF OF ADJACENT AND DOWNSTREAM PROPERTIES AND/OR ADJOINING SITES. AT HIS EXPENSE, THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE REMOVAL OF SEDIMENTS AND DEBRIS ESCAPING THIS PROJECT SITE, THE REMEDIATION AND/OR REPAIR OF ANY DAMAGE THAT MAY OCCUR AS A RESULT TO ADJOINING AND/OR DOWNSTREAM AFFECTED PROPERTIES OR OFFSITE STRUCTURES, AND ANY FINES OR PENALTIES LEVIED AGAINST THE PROJECT BY REGULATORY AGENCIES DUE TO DEFICIENCIES OF CONTROL MEASURES.
17.

ALL DISTURBED AND REGRADED AREAS NOT TO BE PAVED SHALL RECEIVE TOPSOIL AND BE SEEDED AND MULCHED ACCORDING TO GDOT. PERMANENT SEEDING SCHEDULES, COVERED WITH SOLID SOD, OR AS SHOWN ON THE LANDSCAPE PLAN (IF ANY). LOCALIZED EROSION AND RILLS SHALL BE REPAIRED AS NECESSARY AT THE CONTRACTORS EXPENSE. AREAS TO BE SEEDED SHALL RECEIVE 4" OF TOPSOIL AND AREAS TO BE SODDED SHALL RECEIVE 2" (MIN.) OF TOPSOIL. ACCOUNT FOR THICKNESS OF TOPSOIL WITH RESPECT TO FINISHED GRADES.
18.

THESE PLANS EXPRESSLY DELEGATE THE RESPONSIBILITY OF PROPER ON-SITE HAZARDOUS MATERIAL MANAGEMENT TO THE CONTRACTOR. THE CONTRACTOR SHALL AT A MINIMUM PROVIDE AN ACTION PLAN AND KEEP THE NECESSARY MATERIALS ON SITE FOR THE CAPTURE, CLEAN UP, AND DISPOSAL OF ANY PETROLEUM PRODUCT, OR OTHER HAZARDOUS MATERIAL, LEAKS OR SPILLS ASSOCIATED WITH THE SERVICING, REFUELING OR OPERATION OF ANY EQUIPMENT UTILIZED AT THE SITE. A COPY OF THE ACTION PLAN SHALL BE SUBMITTED TO THE PROJECT ENGINEER AND MAINTAINED ON THE PROJECT SITE. ALL PERSONNEL OPERATING OR SERVICING EQUIPMENT SHALL BE FAMILIAR WITH THE ACTION PLAN. THE CONTRACTOR SHALL NOT PARK, REFUEL, OR MAINTAIN EQUIPMENT WITHIN STREAM BUFFERS. IF THE CONTRACTOR ELECTS TO STORE PETROLEUM PRODUCTS ON SITE, THE CONTRACTOR SHALL PREPARE AN ESPCP ADDENDUM THAT ADDITIONAL BMPs NEEDED FOR ONSITE STORAGE AND SPILL PREVENTION FOR PETROLEUM PRODUCTS. THIS PLAN SHALL BE PREPARED BY A CERTIFIED DESIGN PROFESSIONAL AS REQUIRED BY GAR100002 FOR INCLUSION WITH THESE PLANS. THE CONTRACTOR'S ATTENTION IS SPECIFICALLY DIRECTED TO STANDARD SPECIFICATION 107-LEGAL REGULATIONS AND RESPONSIBILITY TO THE PUBLIC FOR ADDITIONAL REQUIREMENTS.
19.

THE WASHING OF READY-MIX CONCRETE DRUMS AND DUMP TRUCK BODIES USED IN THE DELIVERY OF PORTLAND CEMENT CONCRETE IS PROHIBITED ON THIS SITE. IN ACCORDANCE WITH STANDARD SPECIFICATION 107: LEGAL REGULATIONS AND RESPONSIBILITY TO THE PUBLIC, ONLY THE DESCHARGE CHUTE UTILIZED IN THE DELIVERY OF PORTLAND CEMENT CONCRETE MAY BE RINSED FREE OF FRESH CONCRETE REMAINS. THE CONTRACTOR SHALL EXCAVATE A PIT OUTSIDE OF STATE WATER BUFFERS, AT LEAST 25 FEET FROM ANY STORMDRAIN AND OUTSIDE OF THE TRAVELLED WAY, INCLUDING SHOULDERS, FOR A WASH-DOWN PIT. THE PIT SHALL BE LARGE ENOUGH TO STORE ALL WASH-DOWN WATER WITHOUT OVERTOPPING. IMMEDIATELY AFTER THE WASH-DOWN OPERATIONS ARE COMPLETED AND AFTER THE WASH-DOWN WATER HAS SOAKED INTO THE GROUND, THE PIT SHALL BE FILLED IN, AND THE GROUND ABOVE IT SHALL BE GRADED TO MATCH THE ELEVATION OF THE SURROUNDING AREAS. ALTERNATE WASH-DOWN PLANS MUST BE APPROVED BY THE PROJECT ENGINEER.
20.

POST CONSTRUCTION MEASURES INSTALLED DURING THE PROJECT TO CONTROL POLLUTANTS IN STORMWATER WILL INCLUDE ADS FLEX STORM FILTER BAGS INSIDE DESIGNED STORMWATER STRUCTURES, AS WELL AS PERMANENT GRASSING AND VEGETATION.

SOIL EROSION AND SEDIMENTATION CONTROL NOTES:

1.

THE PROJECT IS LOCATED CENTRALLY IN JACKSON COUNTY APPROXIMATELY 4.6 MILES NORTH OF THE CITY OF JEFFERSON GEORGIA AS SHOWN ON THE COVER SHEET AND PLAN SHEETS. THE PROJECT INVOLVES THE CONSTRUCTION OF A NEW HANGAR WITH PARKING LOT AND TURN LANE.
2.

THE RESPONSIBLE PARTY FOR THE EROSION, SEDIMENTATION, AND POLLUTION CONTROL, 24 HR. CONTACT: XXX , PH. (706) XXX-XXXX FAX (706) XXX-XXXX. THE CONTACT INFORMATION FOR THE PRIMARY PERMITTEE, CONTACT: XXXX, PH. (706) XXX-XXXX FAX (706) XXX-XXXX
3.

THE ESCAPE OF SEDIMENT FROM THE SITE SHALL BE PREVENTED BY THE INSTALLATION OF EROSION AND SEDIMENT CONTROL MEASURES AND PRACTICES PRIOR TO, LAND-DISTURBING ACTIVITIES.
4.

THE CONSTRUCTION PAD SHALL BE MAINTAINED IN A CONDITION WHICH WILL PREVENT TRACKING OR FLOW OF MUD ONTO PUBLIC STREETS.
5.

SILT FENCES AND HAY BALE BARRIERS SHALL BE CLEANED OR REPLACED AND MAINTAINED IN FUNCTIONAL CONDITION UNTIL PERMANENT EROSION CONTROL MEASURES ARE ESTABLISHED.
6.

SILT FENCE FABRIC SHALL BE COMPRISED OF GA. DOT QUALIFIED PRODUCTS LIST 36, FOR SILT FENCE FABRIC.
7.

ALL GRASSING SHALL BE IN ACCORDANCE WITH CHAPTER 6, SECTION III "VEGETATIVE PRACTICES" OF THE MANUAL FOR EROSION AND SEDIMENT CONTROL IN GEORGIA.
8.

ALL OTHER WORK SHALL BE PERFORMED IN ACCORDANCE WITH THE MANUAL FOR EROSION AND SEDIMENT CONTROL IN GEORGIA.
9.

THE CONTRACTOR SHALL FURNISH APPROPRIATE AUTHORITY OR DEPT. WITH A SCHEDULE OF ANTICIPATED STARTING AND COMPLETION DATES FOR EACH SEQUENCE OF LAND DISTURBING ACTIVITY LISTED IN ITEMS FOUR THROUGH EIGHT ABOVE.
10.

EROSION CONTROL DEVICES WILL BE IN PLACE BEFORE SITE DISTURBANCE AND WILL BE PERIODICALLY INSPECTED AND REPAIRED OR RESTORED AS NEEDED TO FUNCTION PROPERLY UNTIL PERMANENT MEASURES ARE ESTABLISHED AND PROJECT IS COMPLETE. I.E., CONSTRUCTION EXITS AND SILT FENCES SHALL BE RETOPPED OR CLEANED AS SILT REDUCES THEIR EFFECTIVENESS.
11.

ANY ADDITIONAL CONSTRUCTION OTHER THAN SHOWN ON THIS PLAN WILL REQUIRE SEPARATE AND ADDITIONAL EROSION AND SEDIMENT CONTROL MEASURES AND APPROVAL.
12.

ANY DISTURBED AREA LEFT EXPOSED FOR A PERIOD GREATER THAN 14 DAYS SHALL BE STABILIZED WITH MULCH OR TEMPORARY SEEDINGS.
13.

ALL DISTURBED AREAS WILL BE PERMANENTLY LANDSCAPED AND GRASSED AS SOON AS CONSTRUCTION PHASES PERMIT.
14.

ALL WORK SHALL BE PERFORMED IN ACCORDANCE WITH THE SPECIFICATION OF THE MANUAL FOR EROSION AND SEDIMENT CONTROL IN GEORGIA.
15.

ADDITIONAL MEASURES MAY BE REQUIRED TO CONTROL EROSION AS DETERMINED NECESSARY BY INSPECTORS.
16.

CUT AND FILL SLOPES NOT TO EXCEED 2H:1V.
17.

NOTIFY WATER & SEWER INSPECTOR PRIOR TO START OF CONSTRUCTION.
18.

SEDIMENTATION & EROSION CONTROL MEASURES TO BE INSPECTED DAILY.
19.

EROSION CONTROL MEASURES WILL BE MAINTAINED AT ALL TIMES. IF FULL IMPLEMENTATION OF THE APPROVED PLACE DOES NOT PROVIDE FOR EFFECTIVE EROSION CONTROL, ADDITIONAL EROSION AND SEDIMENT CONTROL MEASURES SHALL BE IMPLEMENTED TO CONTROL OR TREAT THE SEDIMENT SOURCE. PRACTICES WILL BE CHECKED DAILY.
20.

THERE ARE NOT STATE WATERS LOCATED WITHIN 200 FEET OF THE PROJECT SITE.
21.

THE PROJECT DOES NOT IMPACT/DISTURB STATE WATERS, OR STREAMS.
22.

THE PROJECT DOES NOT IMPACT/DISTURB WETLAND AREAS.
23.

ADJACENT PROPERTIES TO THE PROPOSED CONSTRUCTION SITE ARE COMPRISED OF PRIVATE AND COMMERCIAL PROPERTIES.
24.

EXISTING LAND USE AT PROJECT SITE IS CONCRETE, ASPHALT, AND GRASS.
25.

THE DISTURBED AREA FOR THE PROJECT IS 4.687 ACRES. SILT STORAGE REQUIRED IS 4.687 AC. TIMES 67 CY/AC = 314.029 CY. ESTIMATED INSTALLATION OF 1,655.340 LF OF NON-SENSITIVE TYPE "NS" X / 27 CF/CY = 61.31 CY OF SILT BASED ON A 5:1 SLOPE.
26.

THE CONTRACTOR SHALL BE RESPONSIBLE FOR MAINTAINING THE EROSION CONTROL MEASURES FOR THE ENTIRE LENGTH OF THE PROJECT AND SHALL ADD ADDITIONAL MEASURES AS NECESSARY TO PREVENT EROSION AND SEDIMENTATION RUN-OFF FROM THE DISTURBED AREAS.
27.

CONSTRUCTION EXIT WIDTHS MAY BE MODIFIED TO FIT THE WIDTH OF THE LIMITS OF DISTURBANCE (LOD) FOR THIS PROJECT.
28.

THE CONTRACTOR MUST COMPLY WITH NPDES GENERAL PERMIT NO. 100001 - EFFECTIVE AUGUST 1, 2023.
29.

NARRATIVE POLLUTION PREVENTION PRACTICES:  
THE FOLLOWING ARE POTENTIAL SOURCES OF STORM WATER POLLUTION EXPECTED TO BE PRESENT ON THE SITE AND AN EXPLANATION OF HOW THE POLLUTANTS WILL BE MINIMIZED IN THE STORM WATER DISCHARGES: RUNOFF FROM DISTURBED/UNDISTURBED AREAS TO BE MINIMIZED THROUGH THE INSTALLATION OF Sd1 SILT FENCE, Ds1 MULCH, Ds2 TEMPORARY SEEDING AND Ds3 PERMANENT VEGETATION.
30.

"THE DESIGN PROFESSIONAL WHO PREPARED THE ES&PC PLAN IS TO INSPECT THE INSTALLATION OF THE INITIAL SEDIMENT STORAGE REQUIREMENTS AND PERIMETER CONTROL BMPs WITHIN 7 DAYS AFTER INSTALLATION." IN ACCORDANCE WITH PART I.V.A.5 PAGE 25 OF THE PERMIT.
31.

AMMENDMENTS/REVISIONS TO THE ES&PC PLAN WHICH HAVE A SIGNIFICANT EFFECT ON BMPs WITH A HYDRAULIC COMPONENT MUST BE CERTIFIED BY THE DESIGN PROFESSIONAL.

STRUCTURAL PRACTICES

CODE	PRACTICE	DETAIL	MAP SYMBOL	DESCRIPTION
Cd	CHECKDAM			A small temporary barrier or dam constructed across a swale, drainage ditch or area of concentrated flow.
Co	CONSTRUCTION EXIT			A crushed stone pad located at the construction site exit to provide a place for removing mud from tires thereby protecting public streets.
Sd1	SEDIMENT BARRIER			A barrier to prevent sediment from leaving the construction site. It may be sandbags, bales of straw or hay, brush, logs and poles, gravel, or a silt fence.
Sd2	INLET SEDIMENT TRAP			An impounding area created by excavating around a storm drain drop inlet. The excavated area will be filled and stabilized on completion of construction activities.
St	STORMDRAIN OUTLET PROTECTION			A paved or short section of riprap channel at the outlet of a storm drain system preventing erosion from the concentrated runoff.

VEGETATIVE PRACTICES

CODE	PRACTICE	DETAIL	MAP SYMBOL	DESCRIPTION
Ds1	DISTURBED AREA STABILIZATION (WITH MULCHING ONLY)			Establishing temporary protection for disturbed areas where seedlings may not have a suitable growing season to produce an erosion retarding cover.
Ds2	DISTURBED AREA STABILIZATION (WITH TEMP. SEEDING)			Establishing a temporary vegetative cover with fast growing seedlings on disturbed areas.
Ds3	DISTURBED AREA STABILIZATION (WITH PERM. SEEDING)			Establishing a permanent vegetative cover such as trees, shrubs, vines, grasses, or legumes on disturbed areas.
Ds4	DISTURBED AREA STABILIZATION (SODDING)			A permanent vegetative cover using sods on highly erodible or critically eroded lands.
Du	DUST CONTROL ON DISTURBED AREAS			Controlling surface and air movement of dust on construction site, roadways and similar sites.
Ss	SLOPE STABILIZATION			A protective covering used to prevent erosion and establish temporary or permanent vegetation on steep slopes, shore lines, or channels.

I CERTIFY THAT THE PERMITTEE'S EROSION, SEDIMENTATION AND POLLUTION CONTROL PLAN PROVIDES FOR AN APPROPRIATE AND COMPREHENSIVE SYSTEM OF BEST MANAGEMENT PRACTICES REQUIRED BY THE GEORGIA WATER QUALITY CONTROL ACT AND THE DOCUMENT "MANUAL FOR EROSION AND SEDIMENT CONTROL IN GEORGIA" (MANUAL) PUBLISHED BY THE GEORGIA SOIL AND WATER CONSERVATION COMMISSION AS OF JANUARY 1 OF THE YEAR IN WHICH THE LAND-DISTURBING ACTIVITY WAS PERMITTED. PROVIDES FOR THE SAMPLING OF THE RECEIVING WATER(S) OR THE SAMPLING OF THE STORMWATER OUTFALLS AND THAT THE DESIGNED SYSTEM OF BEST MANAGEMENT PRACTICES AND SAMPLING METHODS IS EXPECTED TO MEET THE REQUIREMENTS CONTAINED IN THE GENERAL NPDES PERMIT NO. GAR100001.

SEAN A SHEPHERD  
LEVEL II CERTIFICATION #0081589  
EXPIRES 12/17/2024

I CERTIFY UNDER PENALTY OF LAW THAT THIS PLAN WAS PREPARED AFTER A SITE VISIT TO THE LOCATIONS DESCRIBED HEREIN BY MYSELF OR MY AUTHORIZED AGENT UNDER MY SUPERVISION.

01/26/2024  
Date  
Signed

I CERTIFY THAT THE PERMITTEE'S EROSION, SEDIMENTATION AND POLLUTION CONTROL PLAN PROVIDES FOR THE MONITORING OF: (A) ALL PERENNIAL AND INTERMITTENT STREAMS AND OTHER WATER BODIES SHOWN ON THE USGS TOPOGRAPHIC MAP AND ALL OTHER FIELD VERIFIED PERENNIAL AND INTERMITTENT STREAMS AND OTHER WATER BODIES, OR (B) WHERE ANY SUCH SPECIFIC IDENTIFIED PERENNIAL OR INTERMITTENT STREAM AND OTHER WATER BODY IS NOT PROPOSED TO BE SAMPLED, I HAVE DETERMINED IN MY PROFESSIONAL JUDGMENT, UTILIZING THE FACTORS REQUIRED IN THE GENERAL NPDES PERMIT NO. GAR100001, THAT THE INCREASE IN THE TURBIDITY OF EACH SPECIFIC IDENTIFIED SAMPLED RECEIVING WATER WILL BE REPRESENTATIVE OF THE INCREASE IN THE TURBIDITY OF A SPECIFIC IDENTIFIED UN-SAMPLED RECEIVING WATER.

SEAN A SHEPHERD  
LEVEL II CERTIFICATION #0081589  
EXPIRES 12/17/2024

I CERTIFY UNDER PENALTY OF LAW THAT THIS REPORT AND ALL ATTACHMENTS WERE PREPARED UNDER MY DIRECTION OR SUPERVISION IN ACCORDANCE WITH A SYSTEM DESIGNED TO ASSURE THAT CERTIFIED PERSONNEL PROPERLY GATHER AND EVALUATE THE INFORMATION SUBMITTED. BASED ON MY INQUIRY OF THE PERSON OR PERSONS WHO MANAGE THE SYSTEM, OR THOSE PERSONS DIRECTLY RESPONSIBLE FOR GATHERING THE INFORMATION, THE INFORMATION SUBMITTED IS, TO THE BEST OF MY KNOWLEDGE AND BELIEF, TRUE, ACCURATE, AND COMPLETE. I AM AWARE THAT THERE ARE SIGNIFICANT PENALTIES FOR SUBMITTING FALSE INFORMATION, INCLUDING THE POSSIBILITY OF FINE AND IMPRISONMENT FOR KNOWING VIOLATIONS.

Owner Date

ALPHA SITE SET 10-29-2024



EROSION NOTES

JACKSON COUNTY AIRPORT  
NEW TERMINAL  
JACKSON COUNTY, GEORGIA

ISSUE DATE

CONSTRUCTION DEVELOPMENT  
1/29/2024

Goodwyn Mills Cawood, LLC  
6120 Powers Ferry Road NW, Suite 200  
Atlanta, GA 30339  
T 770.952.2481  
GMCNETWORK.COM



C-405  
sheet X of X

GMC # TATL230006

1/29/2024 11:02:41 AM TEMPLATE VERSION: 2022.1

CMP SAMPLING METHODS & PROCEDURES  
GENERAL PERMIT No. GAR 100001 – EFFECTIVE AUGUST 1, 2023

REPRESENTATIVE SAMPLING ON STAND ALONE CONSTRUCTION PROJECT  
Receiving water samples and storm water discharge samples will be collected by "grab samples", as specified in Part IV.D.6 of the GAR 100001 permit. All "grab samples" will be collected using the following methods and procedures.

SAMPLING REQUIREMENTS:

SAMPLING FREQUENCY:

(1). The primary permittee must sample in accordance with the Plan at least once for each rainfall event described below. For a qualifying event, the permittee shall sample at the beginning of any storm water discharge to a monitored receiving water and/or from a monitored outfall location within forty-five (45) minutes or as soon as possible.

(2). However, where manual and automatic sampling are impossible (as defined in this permit), or are beyond the permittee's control, the permittee shall take samples as soon as possible, but in no case more than twelve (12) hours after the beginning of the storm water discharge.

(3). Sampling by the permittee shall occur for the following qualifying events:

(a). For each area of the site that discharges to a receiving water or from an outfall, the first rain event that reaches or exceeds 0.5 inch with a storm water discharge that occurs during normal business hours as defined in this permit. after all clearing and grubbing operations have been completed, but prior to completion of mass grading operations, in the drainage area of the location selected as the representative sampling location;

(b). In addition to (a) above, for each area of the site that discharges to a receiving water or from an outfall, the first rain event that reaches or exceeds 0.5 inch with a storm water discharge that occurs during normal business hours as defined in this permit either 90 days after the first sampling event or after all mass grading operations have been completed, but prior to submittal of a NOT, in the drainage area of the location selected as the representative sampling location, whichever comes first;

(c). At the time of sampling performed pursuant to (a) and (b) above, if BMPs in any area of the site that discharges to a receiving water or from an outfall are not properly designed, installed and maintained, corrective action shall be defined and implemented within two (2) business days, and turbidity samples shall be taken from discharges from that area of the site for each subsequent rain event that reaches or exceeds 0.5 inch during normal business hours\* until the selected turbidity standard is attained, or until post-storm event inspections determine that BMPs are properly designed, installed and maintained;

(d). Where sampling pursuant to (a), (b) or (c) above is required but not possible (or not required because there was no discharge), the permittee, in accordance with Part IV.D.4.a.(6), must include a written justification in the inspection report of why sampling was not performed. Providing this justification does not relieve the permittee of any subsequent sampling obligations under (a), (b) or (c) above; and

(e). Existing construction activities, i.e., those that are occurring on or before the effective date of this permit, that have met the sampling required by (a) above shall sample in accordance with (b). Those existing construction activities that have met the sampling required by (b) above shall not be required to conduct additional sampling other than as required by (c) above.

\*Note that the Permittee may choose to meet the requirements of (a) and above by collecting turbidity samples from any rain event that reaches or exceeds 0.5 inch and allows for sampling at any time of the day or week.

INSPECTIONS:

(1). Each day when any type of construction activity has taken place at a primary permittee's site, certified personnel provided by the primary permittee shall inspect: (a) all areas at the primary permittee's site where petroleum products are stored, used, or handled for spills and leaks from vehicles and equipment and (b) all locations at the primary permittee's site where vehicles enter or exit the site for evidence of off-site sediment tracking. These inspections must be conducted until a Notice of Termination is submitted.

(2). Measure and record rainfall within disturbed areas of the site that have not met final stabilization once every 24 hours except any non-working Saturday, non-working Sunday and non-working Federal holiday. The data collected for the purpose of compliance with this permit shall be representative of the monitored activity. Measurement of rainfall may be suspended if all areas of the site have undergone final stabilization or established a crop of annual vegetation and a seeding of target perennials appropriate for the region.

(3). Certified personnel (provided by the primary permittee) shall inspect the following at least once every fourteen (14) calendar days and within 24 hours of the end of a storm that is 0.5 inches rainfall or greater (unless such storm ends after 5:00 PM on any Friday or on any nonworking Saturday, non-working Sunday or any non-working Federal holiday in which case the inspection shall be completed by the end of the next business day and/or working day, whichever occurs first): (a) disturbed areas of the primary permittee's construction site ; {b) areas used by the primary permittee for storage of materials that are exposed to precipitation ; and (c) structural control measures. Erosion and sediment control measures identified in the Plan applicable to the primary permittee's site shall be observed to ensure that they are operating correctly. Where discharge locations or points are accessible, they shall be inspected to ascertain whether erosion control measures are effective in preventing significant impacts to receiving water(s). For areas of a site that have undergone final stabilization or established a crop of annual vegetation and a seeding of target perennials appropriate for the region, the permittee must comply with Part IV.D.4.a.(4). These inspections must be conducted until a Notice of Termination is submitted.

INSPECTIONS CONTINUED:

(4). Certified personnel (provided by the primary permittee) shall inspect at least once per month during the term of this permit (i.e., until a Notice of Termination is submitted to EPD) the areas of the site that have undergone final stabilization or established a crop of annual vegetation and a seeding of target perennials appropriate for the region. These areas shall be inspected for evidence of, or the potential for, pollutants entering the drainage system and the receiving water(s). Erosion and sediment control measures identified in the Plan shall be observed to ensure that they are operating correctly. Where discharge locations or points are accessible, they shall be inspected to ascertain whether erosion control measures are effective in preventing significant impacts to receiving water(s).

(5). Based on the results of each inspection, the site description and the pollution prevention and control measures identified in the Erosion, Sedimentation and Pollution Control Plan, the Plan shall be revised as appropriate not later than seven (7) calendar days following each inspection. Implementation of such changes shall be made as soon as practical but in no case later than seven (7) calendar days following each inspection.

(6). A report of each inspection that includes the name(s) of certified personnel making each inspection, the date(s) of each inspection, construction phase (i.e., initial, intermediate or final), major observations relating to the implementation of the Erosion, Sedimentation and Pollution Control Plan, and actions taken in accordance with Part IV.D.4.a.(5). of the permit shall be made and retained at the site or be readily available at a designated alternate location until the entire site or that portion of a construction project that has been phased has undergone final stabilization and a Notice of Termination is submitted to EPD. Such reports shall be readily available by end of the second business day and/or working day and shall identify all incidents of best management practices that have not been properly installed and/or maintained as described in the Plan. Where the report does not identify any incidents, the inspection report shall contain a statement that the best management practices are in compliance with the Erosion, Sedimentation and Pollution Control Plan. The report shall be signed in accordance with Part V.G.2. of this permit.

REPORTING

1. The applicable permittees are required to submit the sampling results to the EPD by the fifteenth day of the month following the reporting period. Reporting periods are months during which samples are taken in accordance with this permit. Sampling results shall be in a clearly legible format. Upon written notification, EPD may require the applicable permittee to submit the sampling results on a more frequent basis. Sampling and analysis of any stormwater discharge(s) or the receiving water(s) beyond the minimum frequency stated in this permit must be reported in a similar manner to the EPD. Sampling reports must be submitted to EPD using the electronic submittal service provided by EPD. Sampling reports must be submitted to EPD until such time as a NOT is submitted in accordance with Part VI.

2. All sampling reports shall include the following information:

- a. The rainfall amount, date, exact place and time of sampling or measurements;
- b. The name(s) of the certified personnel who performed the sampling and measurements;
- c. The date(s) analyses were performed;
- d. The time(s) analyses were initiated;
- e. The name(s) of the certified personnel who performed the analyses;
- f. References and written procedures, when available, for the analytical techniques or methods used;
- g. The results of such analyses, including the bench sheets, instrument readouts, computer disks or tapes, etc., used to determine these results;
- h. Results which exceed 1000 NTU shall be reported as "exceeds 1000 NTU;" and
- i. Certification statement that sampling was conducted as per the Plan.

3. All written correspondence required by this permit shall be submitted by return receipt certified mail (or similar service) to the appropriate District Office of the EPD according to the schedule in Appendix A of this permit. The permittee shall retain a copy of the proof of submittal at the construction site or the proof of submittal shall be readily available at a designated location from commencement of construction until such time as a NOT is submitted in accordance with Part VI.


RETENTION OF RECORDS:

- The primary permittee shall retain the following records at the construction site or the records shall be readily available at a designated alternate location from commencement of construction until such time as a NOT is submitted in accordance with Part VI:
  - a. A copy of all Notices of Intent submitted to EPD;
  - b. A copy of the Erosion, Sedimentation and Pollution Control Plan required by this permit;
  - c. The design professional's report of the results of the inspection conducted in accordance with Part IV.A.5. of this permit;
  - d. A copy of all sampling information, results, and reports required by this permit;
  - e. A copy of all inspection reports generated in accordance with Part IV.D.4.a. of this permit;
  - f. A copy of all violation summaries and violation summary reports generated in accordance with Part III.D.2. of this permit; and
  - g. Daily rainfall information collected in accordance with Part IV.D.4.a.(2). of this permit.
- Copies of all Notices of Intent, Notices of Termination, inspection reports, sampling reports (including all calibration and maintenance records and all original strip chart recordings for continuous monitoring instrumentation), or other reports requested by the EPD, Erosion, Sedimentation and Pollution Control Plans, records of all data used to complete the Notice of Intent to be covered by this permit and all other records required by this permit shall be retained by the permittee who either produced or used it for a period of at least three years from the date that the NOT is submitted in accordance with Part VI of this permit. These records must be maintained at the permittee's primary place of business or at a designated alternative location once the construction activity has ceased at the permitted site. This period may be extended by request of the EPD at any time upon written notification to the permittee.

ALPHA SITE SET 10-29-2024

COMPREHENSIVE  
MONITORING  
PROGRAM  
GENERAL NOTES

C-406  
sheet X of X



JACKSON COUNTY AIRPORT  
NEW TERMINAL  
JACKSON COUNTY, GEORGIA

GMC # TATL23006


ISSUE DATE

1/29/2024

CONSTRUCTION  
DEVELOPMENT

DRAWN BY: Author  
CHECKED BY: Checker

Goodwyn Mills Cawood, LLC  
6120 Powers Ferry Road NW, Suite 200  
Atlanta, GA 30339  
T 770.952.2481  
GMCNETWORK.COM



1/29/2024 11:02:41 AM TEMPLATE VERSION: 2022.1

DESCRIPTION OF ANALYTICAL METHODS TO BE USED TO COLLECT AND ANALYZE THE SAMPLES:

The method used to collect and analyze the water samples shall be in accordance with the following procedures:

- All samples shall be grab samples.
- Analysis of samples must be conducted in accordance with methodology and test procedures established by 40 CFR Part 136 (unless other test procedures have been approved), the guidance document titled "NPDES Storm Water Sampling Guidance Document, EPA 833-B-92-001" and guidance documents that may be prepared by the EPD.
- Sample containers should be labeled prior to collecting the samples.
- Samples should be well mixed before transferring to a secondary container.
- Large mouth, well cleaned and rinsed glass or plastic jars should be used for collecting samples. The jars should be cleaned thoroughly to avoid contamination.
- Manual or automatic sampling may be utilized. Samples required by this permit should be analyzed immediately, but in no case later than 48 hours after collection. However, samples from automatic samplers must be collected no later than the next business day after their accumulation, unless flow through automated analysis is utilized. Samples are not required to be cooled. Dilution of samples is not required. Samples may be analyzed directly with a properly calibrated turbidimeter.
- Sampling and analysis of the receiving water(s) or outfalls beyond the minimum frequency stated in the permit must be reported to EPD as specified in Part IV.E of the permit.
- The upstream sample for each receiving water(s) must be taken immediately upstream of the confluence of the first storm water discharge from the permitted activity but downstream of any other storm water discharges not associated with the permitted activity.
- The downstream sample for each receiving water(s) must be taken downstream of the confluence of the last storm water discharge from the permitted activity but upstream of any other storm water discharge not associated with the permitted activity.
- Samples should be taken from the horizontal and vertical center of the receiving water(s) or the storm water outfall channel(s).
- Care should be taken to avoid stirring the bottom sediments in the receiving water(s) or in the outfall storm water channel.
- The sampling container should be held so that the opening faces upstream.
- The samples should be kept free from floating debris.

Deviations from these methods and procedures shall be documented by the primary permittee.

Sampling must be done in such a way as to accurately reflect whether storm water runoff from the site is in compliance with the standard set forth in the permit.

Measurement of rainfall must be recorded daily (once each twenty-four hour period) at the site.

The primary permittee must sample all perennial and intermittent streams and other water bodies or all outfalls into such streams and other water bodies as indicated on the map referenced in the permit.

For STAND ALONE construction projects, monitoring obligations shall cease for any phase of the project that has been stabilized in accordance with Part IV.D.6.c.(1).(g).

NTU MATRIX VALUE

The proposed development has a surface water drainage area of X.XX sq.m which is between 0-4.99 square miles and a site size (4.687 ac.) between 1.00-10.00 acres. See table below. The NTU value selected is 75.

Site Size, acres	Waters Supporting Warm Water Fisheries							
	Surface Water Drainage Area, square miles							
	0-4.99	5-9.99	10-24.99	25-49.99	50-99.99	100-249.99	250-499.99	500+
1.00-10	75	150	200	400	750	750	750	750
10.01-25	50	100	100	200	300	500	750	750
25.01-50	50	50	100	100	200	300	750	750
50.01-100	50	50	50	100	100	150	300	600
100.01+	50	50	50	50	50	100	200	100

WATERSHED, SITE MONITORING LOCATIONS AND DRAINAGE AREA MAP

SCALE: 1" = 500'

SAMPLING POINTS:

For this project a single representative outfall will be sampled for the stand alone park construction in accordance with current NPDES General Permit No. GAR 100001.

The project is located in Meriwether County GA. approximately 1.5 miles north of the City of Greenville, more particularly along the southerly r/w of McLaughlin Road as indicated on the location map and plan sheets. There are (3) THREE outfall areas for this project and they have a combined total drainage area of 59.85 acres. The runoff from the project drains to an unnamed tributary of the Kennel Creek.

Drainage Basin (Ac)	Disturbed Area (Ac)	Monitoring Station location
"A" = 21.68 (0.03 SQ. MI.)	1.218	DETENTION POND #1 OUTFALL
"B" = 13.99 (0.02 SQ. MI.)	2.639	DETENTION POND #2 OUTFALL
"C" = 24.18 (0.04 SQ. MI.)	6.293	N/A

The aforementioned tributary is a continuously flowing stream. The (2) TWO sampling locations are representative for the project.

The sampling location for the disturbed drainage basin above shall be monitored concurrent with land disturbance/clearing. Sampling is required during construction and until all disturbed areas are stabilized. Permanent/Final Stabilization is defined as 100% cover with 70% density of the disturbed soil surface uniformly covered in permanent vegetation or equivalent permanent stabilization measures (such as the use of rip rap, gabions, permanent mulches or geotextiles) have been employed.

Note: The monitor shall be located at the outlet structure pipe as called out on this plan or as directed by the engineer and/or Georgia EPD. A total of (2) TWO monitors shall be installed for this project. The NTU value allowed for this project is 50 is determined from the Appendix B table.

SOIL MAP



SITE SPECIFIC SOIL SURVEY IS AVAILABLE UPON REQUEST

JACKSON COUNTY AIRPORT



VICINITY MAP

RIP RAP OUTLET PROTECTION:

Outlet Protection - St		
Structure	A-07	A-09
Q [cfs]	11.71	3.75
Pipe [in.]	18	18
V [fps]	7.76	4.32
La [ft.]	12.0	9.0
W [ft.] (up)	4.5	4.5
W [ft.] (down)	13.5	10.5
d50 [in.]	6	6
Depth [in.]	12	12
*based on 25-year storm event		

EROSION NOTES

JACKSON COUNTY AIRPORT  
NEW TERMINAL  
JACKSON COUNTY, GEORGIA

ISSUE DATE

CONSTRUCTION DEVELOPMENT

1/29/2024

GMC # TATL230006

DRAWN BY: Author  
CHECKED BY: Checker

NOT FOR CONSTRUCTION


C-407  
sheet X of X

Plan		Included	
Page #	Y/N		
C-406	Y	1	The applicable Erosion, Sedimentation and Pollution Control Plan Checklist established by the Commission as of January 1 of the year in which the land-disturbing activity was permitted.
C-405	Y	2	Level II certification number issued by the Commission, signature and seal of the certified design professional.
C-405	N/A	3	Limits of disturbance shall be no greater than 50 acres at any one time without prior written authorization from the GAEPD District Office. If GAEPD approves the request to disturb 50 acres or more at any one time, the Plan must include at least 4 of the BMPs listed in Appendix 1 of this checklist and the GAEPD approval letter. *
C-405	Y	4	The name and phone number of the 24-hour contact responsible for erosion, sedimentation and pollution controls.
C-405	Y	5	Provide the name, address, email address, and phone number of primary permittee.
C-405	Y	6	Note total and disturbed acreages of the project or phase under construction.
C-401	Y	7	Provide the GPS location of the construction exit for the site. Give the Latitude and Longitude in decimal degrees.
C-401	Y	8	Initial date of the Plan and the dates of any revisions made to the Plan including the entity who requested the revisions.
C-405	Y	9	Description of the nature of construction activity and existing site conditions.
		10	Provide vicinity map showing site's relation to surrounding areas. Include designation of specific phase, if necessary.
N/A	N/A	11	Identify the project receiving waters and describe all sensitive adjacent areas including streams, lakes, residential areas, wetlands, marshlands, etc. which may be affected.
C-405	Y	12	Design professional's certification statement and signature that the site was visited prior to development of the ES&PC Plan as stated on <b>Part IV page 19</b> of the permit.
C-405	Y	13	Design professional's certification statement and signature that the permittee's ES&PC Plan provides for an appropriate and comprehensive system of BMPs and sampling to meet permit requirements as stated on <b>Part IV page 19</b> of the permit. *
C-405	Y	14	Clearly note the statement that "The design professional who prepared the ES&PC Plan is to inspect the installation of the initial sediment storage requirements and perimeter control BMPs within 7 days after installation." in accordance with <b>Part IV.A.5 page 25</b> of the permit. *
N/A	N/A	15	Clearly note the statement that "Non-exempt activities shall not be conducted within the 25 or 50-foot undisturbed stream buffers as measured from the point of wrested vegetation or within 25-feet of the coastal marshland buffer as measured from the Jurisdictional Determination Line without first acquiring the necessary variances and permits."
N/A	N/A	16	Provide a description of any buffer encroachments and indicate whether a buffer variance is required.
C-405	Y	17	Clearly note the statement that "Amendments/revisions to the ES&PC Plan which have a significant effect on BMPs with a hydraulic component must be certified by the design professional." *
C-405	Y	18	Clearly note the statement that "Waste materials shall not be discharged to waters of the State, except as authorized by a Section 404 permit" *
C-405	Y	19	Clearly note statement that "The escape of sediment from the site shall be prevented by the installation of erosion and sediment control measures and practices prior to land disturbing activities."
C-405	Y	20	Clearly note statement that "Erosion control measures will be maintained at all times. If full implementation of the approved Plan does not provide for effective erosion control, additional erosion and sediment control measures shall be implemented to control or treat the sediment source."
C-405	Y	21	Clearly note the statement "Any disturbed area left exposed for a period greater than 14 days shall be stabilized with mulch or temporary seeding."
N/A	N/A	22	Any construction activity which discharges storm water into an Impaired Stream Segment, or within 1 linear mile upstream of and within the same watershed as, any portion of a Biota Impaired Stream Segment must comply with Part III. C. of the permit. Include the completed Appendix 1 listing all the BMPs that will be used for those areas of the site which discharge to the Impaired Stream Segment. *
N/A	N/A	23	If a TMDL Implementation Plan for sediment has been finalized for the Impaired Stream Segment (identified in Item 22 above) at least six months prior to submittal of NOI, the ES&PC Plan must address any site-specific conditions or requirements included in the TMDL Implementation Plan. *
C-405	Y	24	BMPs for concrete washdown of tools, concrete mixer chutes, hoppers and the rear of the vehicles. Washout of the drum at the construction site is prohibited. *
C-405	Y	25	Provide BMPs for the remediation of all petroleum spills and leaks.
C-405	Y	26	Description of the measures that will be installed during the construction process to control pollutants in storm water that will occur after construction operations have been completed. *
C-405	Y	27	Description of practices to provide cover for building materials and building products on site. *
C-405	Y	28	Description of the practices that will be used to reduce the pollutants in storm water discharges. *
N/A	N/A	29	Description and chart or timeline of the intended sequence of major activities which disturb soils for the major portions of the site (i.e., initial perimeter and sediment storage BMPs, clearing and grubbing activities, excavation activities, utility activities, temporary and final stabilization).
C-406	Y	30	Provide complete requirements of Inspections and record keeping by the primary permittee. *

[illegible]

**PLANTING REQUIREMENTS:**

PROPOSED PARKING SPACES:	29
TREES REQUIRED:	3 (1 TREE FOR 10 PARKING SPACES)
TREES PROVIDED:	3
REQUIREMENTS MET:	YES



Jackson County Airport Terminal

GMC Project #: AATI 230012



## PLANTING PLAN

# 1.01

#### A. GENERAL

#### A. GENERAL

1. THE LANDSCAPE DESIGN SHALL SERVE AS THE LIMITS OF IRRIGATION. THE CONTRACTOR IS RESPONSIBLE FOR THE IRRIGATION DESIGN SO IT MEETS THE REQUIREMENTS OF THE REQUIREMENTS OF THE FOLLOWING STANDARDS.
2. PROVIDE AND COMPLETE AN OPERABLE SYSTEM FOR THE IRRIGATION OF ALL LANDSCAPED AREAS ON THE PROJECT SITE, UNLESS INDICATED OTHERWISE.
3. THE CONTRACTOR SHALL BE RESPONSIBLE FOR ADJUSTING HEAD LOCATION, HEAD/NOZZLE TYPE AND SIZE, AND ANY OTHER SYSTEM COMPONENTS SO THAT IRRIGATION SYSTEM LAYOUT IS COORDINATED WITH ACTUAL FIELD CONDITIONS. SUCH ADJUSTMENTS SHALL BE COMPENSATED FOR AT AN AGREED COST.
4. CONTRACTORS SHALL PROVIDE WITH THE BID A SAMPLE DESIGN INDICATING THE SCHEMATIC LOCATION OF EACH ZONE, THE QUANTITY AND TYPE OF SPRINKLERS TO BE USED.
5. CONTRACTORS SHALL SPECIFY WITH THE BID THE MANUFACTURERS OF THE CONTROLLER, VALVES, AND SPRINKLERS.
6. COMPLY WITH ALL CODES, ORDINANCES AND REQUIREMENTS OF AUTHORITIES HAVING JURISDICTION.
7. OBTAIN ALL REQUIRED PERMITS AND PAY ALL REQUIRED FEES, AT NO ADDITIONAL COST TO THE OWNER, PENALTIES IMPOSED DUE TO FAILURE TO OBTAIN PERMITS OR PAY FEES ARE THE RESPONSIBILITY OF THE CONTRACTOR.
8. ALL WORK SHALL BE WARRANTED BY THE CONTRACTOR FOR A PERIOD OF ONE YEAR AGAINST DEFECTS IN MATERIAL, EQUIPMENT, WORKMANSHIP AND ANY REPAIRS RESULTING FROM LEAKS OR OTHER DEFECTS OF WORKMANSHIP, MATERIALS OR EQUIPMENT.
9. SUBMIT SHOP DRAWINGS SHOWING IRRIGATIONS SYSTEM, INCLUDING PLAN LAYOUT AND LOCATIONS, TYPES, SIZES, CAPACITIES, AND FLOW CHARACTERISTICS OF IRRIGATION SYSTEM COMPONENTS.
10. SUBMIT "AS-BUILT" DRAWING AT COMPLETION OF WORK SHOWING LOCATIONS OF ALL VALVES, HOSE BIBS AND WIRE SPLICES, WITH AN ACCURATE TRIANGULATED DIMENSIONS, AS WELL AS ANY DEVIATIONS ON LOCATION OF PIPING.
11. LOCATE AND VERIFY ALL UTILITY LOCATIONS ON AND AROUND THE SITE PRIOR TO WORK. MAINTAIN EXISTING UTILITIES AND PROTECT THEM AGAINST DAMAGE DURING THE WORK.
12. CONTRACTOR SHALL MAKE ANY NECESSARY ADJUSTMENTS IN THE PROPOSED IRRIGATION SYSTEM TO AVOID DAMAGE TO EXISTING STRUCTURES, PAVING AND UTILITIES.
13. THE CONTRACTOR SHALL BE RESPONSIBLE FOR ANY DAMAGE TO EXISTING STRUCTURES, PAVING, UTILITIES AND / OR OTHER CONSTRUCTION RESULTING FROM IRRIGATION CONSTRUCTION.
14. THE CONTRACTOR SHALL BE RESPONSIBLE FOR ALL MATERIALS AND LABOR TO FULLY EXECUTE AND GUARANTEE THE WORK AS REQUIRED. THE LIMITS OF WORK SHOWN ON THESE DRAWINGS SHALL BE IRRIGATED IN ACCORDANCE WITH THE SPECIFICATIONS AND PER THE DIRECTION GIVEN TO THE OWNER OR LANDSCAPE ARCHITECT.
15. ALL ADJUSTMENTS TO THE WORK SHALL BE SUBJECT TO THE APPROVAL OF THE OWNER OR THE LANDSCAPE ARCHITECT.
16. IRRIGATION CONTRACTOR WILL BE RESPONSIBLE FOR CONTACTING THE LANDSCAPE CONTRACTOR AND COORDINATING THE LAYOUT OF THE IRRIGATION SYSTEM WITH THE LANDSCAPE BED LINES PRIOR TO INSTALLATION.
17. INSTALL BACKFLOW PREVENTOR BELOW GRADE MEETING REQUIREMENTS OF LOCAL AUTHORITIES HAVING JURISDICTION UNLESS OTHERWISE REQUIRED BY JURISDICTION.
18. LOCATE ALL IRRIGATION PIPING IN SUCH A WAY AS TO CAUSE THE LEAST CONFLICT WITH THE LOCATION OF PLANT MATERIALS AND OTHER SITE IMPROVEMENTS.
19. MAIN LINE PIPING SHALL BE INSTALLED A MAXIMUM OF TWO (2) FEET FROM THE BACK OF CURB. LATERAL LINE PIPING SHALL BE INSTALLED SIMILARLY WHERE POSSIBLE.
20. ALL VALVE BOXES SHALL BE LOCATED IN PLANT BEDS OR NATURAL AREAS. EXCEPTION WILL BE ALLOWED IF NO SUCH AREA IS WITHIN A 40-FOOT RADIUS OF THE DESIGNATED CONTROL VALVE LOCATION. NO MORE THAN TWO VALVE BOXES ARE TO BE LOCATED IN ONE PLANT BED OR NATURAL AREA.
21. ALL SWING JOINTS SHALL BE OF RIGID ELBOW TYPE CONSTRUCTION. FLEX PIPE AND PHUNNY PIPE IS NOT ACCEPTABLE.
22. THE IRRIGATION CONTRACTOR SHALL BE RESPONSIBLE FOR COORDINATING WITH THE OWNER ON THE ELECTRICAL REQUIREMENTS AND LOCATION THEREOF FOR THE IRRIGATION CONTROL CLOCK. IRRIGATION CONTRACTOR SHALL BE RESPONSIBLE FOR ALL ELECTRICAL CONNECTIONS FROM THE 120 VAC SERVICE PROVIDED TO THE CONTROL CLOCK AND THE 24 VOLT FIELD WIRING TO THE CONTROL CLOCK.
23. THE LOCATION OF THE CONTROL CLOCK SHALL BE COORDINATED WITH THE OWNER.
24. THE CONTRACTOR SHALL ADJUST THE RADIUS AND ARC OF EACH SPRINKLER TO MINIMIZE "OVER THROU" AND TO ELIMINATE "SPOTS".
25. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE SUPPLY AND INSTALLATION OF ADDITIONAL HEADS NEEDED TO "COVER" DRY SPOTS. THE LOCATION AND ARRANGEMENT OF THESE HEADS SHALL BE SUBJECT TO APPROVAL OF THE OWNER OR LANDSCAPE ARCHITECT.

## B. SLEEVING

1. IRRIGATION SLEEVING SHALL BE PROVIDED AND INSTALLED BY THE IRRIGATION CONTRACTOR
2. THE CONTRACTOR SHALL BE RESPONSIBLE FOR ANY DAMAGE TO EXISTING UTILITIES, STRUCTURES, OR OTHER CONSTRUCTION RESULTING FROM INSTALLATION OF SLEEVES.
3. ANY MODIFICATIONS TO THE SLEEVING IS SUBJECT TO THE APPROVAL OF THE OWNER OR THE LANDSCAPE ARCHITECT.
4. ALL SLEEVES SHALL BE CLASS 160 SOLVENT WELD PVC PIPE OR SCHEDULE 80 PVC PIPE, AS PER THE SPECIFICATIONS.
5. SLEEVES SHALL BE STRAIGHT, LEVEL, AND THE SHORTEST LENGTH POSSIBLE. THE CONTRACTOR SHALL MAKE ANY ADJUSTMENT NECESSARY TO ACCOMMODATE EXISTING VEGETATION, UTILITIES, OR OTHER MAJOR CONSTRUCTION.
6. THERE SHALL BE NO TURNS OR BENDS IN THE SLEEVES.
7. BACKFILL MATERIAL PLACED AROUND THE SLEEVES SHALL BE FREE OF ROCKS OR OTHER FOREIGN MATTER THAT MAY CAUSE DAMAGE TO THE PIPE. TRENCH BACKFILL SHALL BE THOROUGHLY COMPACTED SUCH THAT NO SETTLEMENT OF FINISHED GRADE OCCURS.
8. SLEEVES SHALL BE INSTALLED AT A DEPTH OF AT LEAST 24 INCHES BELOW PAVEMENT SURFACE, AND NO DEEPER THAN 36 INCHES. END OF THE SLEEVE SHALL EXTEND 18 INCHES BEYOND CURB OR PAVEMENT EDGE (SEE DETAIL).
9. THE CONTRACTOR SHALL INSTALL A VERTICAL STUB THAT IS AT LEAST 18 INCHES ABOVE GRADE AT EACH END OF THE SLEEVE TO MARK ITS EXACT LOCATION.
10. ONCE THE SLEEVING IS INSTALLED, THE CONTRACTOR SHALL INSTALL A TEMPORARY CAP ON EACH END OF THE SLEEVE TO MARK ITS EXACT LOCATION.
11. THE CONTRACTORS SHALL LOCATE AND UNCOVER THE ENDS OF ALL SLEEVES.

### C. SYSTEM PERFORMANCE REQUIREMENTS


1. IRRIGATION ZONE CONTROLS SHALL BE AUTOMATIC OPERATION WITH CONTROLLER AND AUTOMATIC CONTROL VALVES.
2. GENERAL IRRIGATION COVERAGE IS NOT ACCEPTABLE.
3. ALL TURF, SHRUB / GROUND COVER BEDS AND SEASONAL COLOR BEDS SHALL BE IRRIGATED AND CONTROLLED SEPARATE ZONES.
4. MINIMUM WATER COVERAGE NOT LESS THAN"
  - a. TURF AREAS: 100 PERCENT
  - b. OTHER PLANTIN AREAS: 70 PERCENT
5. COMPONENTS AND INSTALLATION: CAPABLE OF PRODUCING PIPING SYSTEMS WITH THE FOLLOWING MINIMUM WORKING PRESSURE RATINGS:
  - a. PRESSURE PIPING: 200 PSIG
  - b. CIRCUIT AND DRAIN PIPING: 150 PSIG
  - c. DRAIN PIPING: 100 PSIG
- 6.

4. CONTRACTOR SHALL CONDUCT & SUBMIT TO THE LANDSCAPE ARCHITECT AN ANALYSIS OF A MINIMUM OF (3)


1. CONTRACTOR SHALL CONDUCT & SUBMIT TO THE LANDSCAPE ARCHITECT AN ANALYSIS OF A MINIMUM OF (3) SAMPLES OF EXISTING SOIL FROM AREAS TO BE PLANTED. THE ANALYSIS SHALL BE DONE BY A SOIL TESTING LAB APPROVED BY THE LANDSCAPE ARCHITECT IN ADVANCE AND SHALL INCLUDE THE FOLLOWING RESULTS WITH RECOMMENDATIONS:
  - A. S14 - ORGANIC MATTER, AVAILABLE PHOSPHORUS, EXCHANGEABLE POTASSIUM, MAGNESIUM, CALCIUM, SOIL PH, CATION EXCHANGE CAPACITY, PERCENT BASE SATURATION OF CATION ELEMENTS.
  - B. S3 - SULFUR, ZINC, MANGANESE, IRON, COPPER, BORON
  - C. TEXTURE ANALYSIS
2. TOPSOIL (& PLANTING SOIL WHEN DIFFERENT) SHALL BE PROVIDED MIXED AND READY FOR INSTALLATION. TOPSOIL SHALL MEET THE FOLLOWING CRITERIA & STRIPPED/STOCKPILED TOPSOIL MAY BE USED IF IT CAN REASONABLY BE BROUGHT UP TO THESE CRITERIA.
  - A. FERTILE, FRIABLE, NATURALLY OCCURRING, FREE OF TRASH, ROCKS/STONES, & DEBRIS LARGER THAN 2 INCHES IN ANY DIMENSION.
  - B. FREE OF ANY GRASSES, WEEDS, SEEDS, PLANTS, & ANY SUBSTANCE HARMFUL TO PLANT GROWTH.
  - C. pH RANGE OF 5.0-7.0
  - D. ORGANIC MATTER: 5-10%
  - E. SAND: 50-70%, SILT: LESS THAN 30%, CLAY: 10-25%
  - F. PERMEABILITY RATE OF 30X (-3) CENTIMETERS OR GREATER AT 85% CAPACTION.
3. CONTRACTOR SHALL COORDINATE WITH OWNERS REPRESENTATIVE THE LOCATION OF STOCKPILE AREAS FOR STRIPPED TOPSOIL AND PLANTING SOIL PRODUCTS. CONTRACTOR SHALL ENSURE AREA IS PROTECTED FROM CONTAMINATION & DISTURBANCE
4. FINAL GRADES DEPICTED ON THE GRADING PLAN (REFER TO CIVIL DRAWINGS) ARE TO ACCOUNT FOR PLANTING SOIL DEPTHS INDICATED IN THE LANDSCAPE DRAWINGS/DETAILS. CONTRACTOR SHALL ENSURE SUBGRADE IS SCARIFIED PRIOR TO INSTALLING PLANTING SOIL.
5. FINAL FINISHED GRADING SHALL BE REVIEWED BY THE LANDSCAPE ARCHITECT. CONTRACTOR IS RESPONSIBLE FOR ANY ADDITIONAL TOPSOIL REQUIRED TO CREATE A SMOOTH CONTINUOUS SUIABLE FOR PLANTING.
6. ALL TRASH, DEBRIS LARGER THAN 2 INCHES IN DIAMETER IN ANY DIRECTION, ROCK, COBBLE, EXCAVATION SPOILS, & GRAVEL SHALL BE REMOVED AND LEGALLY DISPOSED OF OFF-SITE PRIOR TO THE INSTALLATION OF TOPSOIL/PLANTING SOIL.
7. COORDINATE INSTALLATION OF TOPSOIL/PLANTING SOIL WITH OTHER WORK. PLACEMENT SHALL OCCUR AFTER INSTALLATION OF HARDCAPE IMPROVEMENTS, IRRIGATION SYSTEMS, UTILITIES, ETC. AND BEFORE PLANT INSTALLATION.
8. PRIOR TO PLANT INSTALLATION, PLANT BEDS AND PITS SHALL BE TESTED FOR PERCOLATION BY THE CONTRACTOR AT NO ADDITIONAL COST TO OWNER. TEST SHALL CONSIST OF 1 FT DIAMETER BY 1 FT DEEP MIN HOLE, OR THE LANTING PIT, FILLED WITH WATER. IF WATER HAS NOT DISSIPATED BY 50% WITHIN 2 HOURS, NOTIFY THE LANDSCAPE ARCHITECT IN WRITING PRIOR TO INSTALLATION. IN HARDPAN CONDITIONS, INSTALL DRAIN PIPES AS PER PLANTING DETAILS.

1. PLANT NAMES MAY BE ABBREVIATED ON DRAWINGS. REFER TO PLANT SCHEDULE FOR ABBREVIATIONS, BOTANICAL & COMMON NAMES, SIZES, ESTIMATED QUANTITIES AND OTHER REMARKS.


2. CONTRACTOR SHALL VERIFY THE TOTAL QUANTITIES INDICATED IN THE PLANT LIST WITH THE QUANTITIES SHOWN ON THE PLAN. CONTRACTOR SHALL PROVIDE QUANTITIES REQUIRED TO COMPLETE PROPOSED PLANTING AS INDICATED ON THE PLAN.
3. CONTRACTOR SHALL GIVE THE LANDSCAPE ARCHITECT THE OPPORTUNITY TO TAG & REVIEW TREES IN THE NURSERY OR FIELD PRIOR TO DIGGING.
4. ALL PLANT/ROOTBALL SIZES & THE METHOD OF DETERMINING TREE CALIPER SHALL CONFORM TO THE RECOMMENDATIONS OF THE LATEST EDITION OF ANSI Z60.1 - AMERICAN STANDARD FOR NURSERY STOCK.
5. ANY & ALL PLANT SUBSTITUTIONS SHALL BE APPROVED BY THE LANDSCAPE ARCHITECT PRIOR TO PURCHASE & INSTALLATION.
6. THE LANDSCAPE ARCHITECT MAY REJECT ANY PLANT AT ANY TIME UNTIL THE END OF THE WARRANTY PERIOD. PLANTS THAT RECEIVED A PRIOR APPROVAL ARE NOT EXCLUDED FROM REJECTION AT A LATER DATE. GROUNDS FOR REJECTION INCLUDE BUT ARE NOT LIMITED TO:
  - A. NON-CONFORMANCE WITH CRITERIA DESCRIBED IN PLANT SCHEDULE.
  - B. THE PRESENCE, EVIDENCE, OR DAMAGE FROM DISEASE, INSECTS/PESTS, EGGS, & LARVAE.
  - C. GIRDLED & KINKED ROOTS, CRACKED/BROKEN ROOT BALLS, MECHANICALLY DAMAGED ROOTS.
  - D. BROKEN LIMBS, INCLUDED BARK, OR EVIDENCE OF MECHANICAL INJURY.
  - E. PLANTS THAT ARE NOT FULFILLING, WELL BRANCHED, OR SYMMETRICAL UNLESS IT IS UNCHARACTERISTIC OF SPECIFIED SPECIES.
  - F. PLANTS DETERMINED AT THE DISCRETION OF THE LANDSCAPE ARCHITECT TO BE AESTHETICALLY DEAD WHERE APPROXIMATELY 25% OR MORE OF THE PLANT IS SHOWING SIGNS OF DEATH/DIEBACK.
7. SHIPMENT TO THE SITE IN UNCOVERED VEHICLES/TRAILERS REGARDLESS OF SEASON.
8. REMOVE FROM SITE ANY & ALL EXISTING VEGETATION INCLUDING STUMPS & ROOTS IN CONFLICT WITH PLANTING PLAN UNLESS EXPLICITLY DESIGNATED FOR PROTECTION.
9. LAYOUT ALL TREES & BED-LINES AS INDICATED IN THE LANDSCAPE DRAWINGS AND RECEIVE APPROVAL FROM THE LANDSCAPE ARCHITECT PRIOR TO INSTALLATION. LAYOUT SHALL BE DONE WITH HIGH VISIBILITY FLAGS AND/OR WOODEN STAKES & BED-LINES SHALL BE LAID OUT WITH MARKING PAINT. THE LANDSCAPE ARCHITECT RESERVES THE RIGHT TO MAKE ANY CHANGES AS NECESSARY AT NO ADDITIONAL COST TO OWNER. NOTIFY LANDSCAPE ARCHITECT OF CONTEMPLATED ADJUSTMENTS TO THE LAYOUT & RECEIVE APPROVAL PRIOR TO COMMENCING WITH ADJUSTMENT.
10. DO NOT INSTALL PLANTS IN SATURATED OR FROZEN CONDITIONS. DO NOT INSTALL PLANTS DURING INCLEMENT WEATHER.
11. SET ALL PLANTS PLUMB & TURNED SO THAT THE MOST ATTRACTIVE SIDE IS MOST COMMONLY VIEWED. MAINTAIN IN PLUMB POSITION THROUGHOUT WARRANTY PERIOD.
12. ALL PLANTING BEDS AND TREES SHALL BE MULCHED WITH 3-4 IN. OF SETTLED PINE STRAW THAT IS FREE FROM DEBRIS, LEAVES, TWIGS, INSECTS, GRASSES, WEEDS, PLANTS AND THEIR SEEDS, AND ANY SUBSTANCE HARMFUL TO PLANT GROWTH. PINE STRAW MULCH SHALL BE TUCKED & ROLLED AT ALL EDGES.
13. TREES GROWN IN SODDED/TURF GRASS AREAS SHALL BE MULCHED WITH AN 8 FT. DIAMETER MULCH RING UNLESS OTHERWISE NOTED ON PLANS.
14. CONTRACTOR TO PROVIDE INTERIM MAINTENANCE UNTIL SUBSTANTIAL COMPLETION NOTICE IS PROVIDED BY THE LANDSCAPE ARCHITECT. THIS INCLUDES:
  - A. WATERING
  - B. MOWING, TRIMMING, EDGING, BLOWING & WEEDING.
  - C. FERTILIZING & APPLICATION OF NECESSARY INSECTICIDES/HERBICIDES
  - D. GUYING TREES WHEN DIRECTED BY OWNER OR LANDSCAPE ARCHITECT.
  - E. ADEQUATE DRAINAGE OF PONDING AREAS.
  - F. GENERAL LANDSCAPE CLEAN-UP.




## 1 TREE PLANTING

$$3/8" = 1'-0"$$


## 2 SHRUB PLANTING

$$\frac{3}{4}'' = 1'-0''$$


### 3 SOD INSTALLATION

$$1\frac{1}{2}'' = 1'-0''$$


6120 Powers Ferry Road NW, Suite 350  
Atlanta, GA 30339  
T 770.952.2481  
GMCNETWORK.COM

[illegible]

**Jackson County Airport Terminal**  
Jackson County, GA

**GMC Project #: AATL230012**



## LANDSCAPE DETAILS

# L2.01

# ALPHA SITE SET 10-29-2024